



Illinois Department of Transportation

Division of Aeronautics

1 Langhorne Bond Drive / Capital Airport / Springfield, Illinois / 62707-8415

July 20, 2016

SUBJECT: Waukegan National Airport
Waukegan, Illinois
Lake County
Illinois Project Number: UGN-4521
SBG Project Number: 3-17-SBGP-xx
Contract No. WA071
Item No. 18A, July 29, 2016 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

Reason for Addendum:

This addendum has been issued to correct the appropriate pay item number for two (2) pay items. The Pay Item Number AR800987 is changed to AR803011. The Pay Item Number Ar800988 is changed to AR803012. The remaining information - description, unit, and as bid quantity - for each item remains unchanged.

To All Plan Holders:

SCHEDULE OF PRICES

The Bidder shall use the attached revised Schedule of Prices when preparing and submitting his bid.

CONSTRUCTION PLAN CHANGES

Replace Plan Sheet 2 of the Construction Plans with the Revised Plan Sheet 2, attached.

- This changes the fifth from the last pay item in the Summary of Quantities table to read:

From:

OLD

AR800987 Relocate Lighted Sign Each 2.0

To:

NEW

AR803011 Relocate Lighted Sign Each 2.0

- This changes the fourth from the last pay item in the Summary of Quantities table to read:

From:

OLD
AR800988 Relocate Unlighted Sign Each 6.0

To:

NEW
AR803012 Relocate Unlighted Sign Each 6.0

SPECIAL PROVISION CHANGES

Replace Page 93 of the Special Provisions with the Revised Page 93, attached.

- This changes the next to the last pay item listed in Section 125-5.1 to read:

From:

OLD
AR800987 Relocate Lighted Sign – per each.

To:

NEW
AR803011 Relocate Lighted Sign – per each.

- This changes the last pay item listed in Section 125-5.1 to read:

From:

OLD
AR800988 Relocate Unlighted Sign - per each.

To:

NEW
AR803012 Relocate Unlighted Sign – per each.

Prime contractors must utilize the enclosed material when preparing their bid **and must include any Schedule of Prices changes in their bidding proposal.**

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Questions on this addendum may be directed to Mr. Ronald M. Hudson, Project Manager, of Hanson Professional Services Inc., at 630.368.2059, or at rhudson@hanson-inc.com.

STATE JOB #- - - -

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - WA071

ECMS002 DTGECM03 ECMR003 PAGE 1
 RUN DATE - 07/06/16
 RUN TIME - 223326

COUNTY NAME	CODE	DIST	AIRPORT NAME	FED PROJECT	ILL PROJECT
LAKE	097	01	WAUKEGAN NATIONAL	3-17-SBGP-XX	UG-N -4521

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	7,879.000	X	=		
AR108960	REMOVE CABLE	L.F.	2,737.000	X	=		
AR110504	4-WAY CONCRETE ENCASED DUCT	L.F.	59.000	X	=		
AR110551	EXTEND DUCT	L.F.	124.000	X	=		
AR110900	REMOVE DUCT	L.F.	60.000	X	=		
AR125410	MITL-STAKE MOUNTED	EACH	43.000	X	=		
AR125415	MITL-BASE MOUNTED	EACH	11.000	X	=		
AR125565	SPLICE CAN	EACH	2.000	X	=		
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	52.000	X	=		
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	7.000	X	=		
AR125906	REMOVE SPLICE CAN	EACH	1.000	X	=		
AR125941	ADJUST STAKE MOUNTED LIGHT	EACH	10.000	X	=		
AR125942	ADJUST BASE MOUNTED LIGHT	EACH	2.000	X	=		
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1.000	X	=		
AR150530	TRAFFIC MAINTENANCE	L.S.	1.000	X	=		

WAUKEGAN NATIONAL
LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - WA071

ECMS002 DTGECM03 ECMR003 PAGE 2
RUN DATE - 07/06/16
RUN TIME - 223326

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	4,514.000 X		=		
AR156510	SILT FENCE	L.F.	880.000 X		=		
AR156513	SEPARATION FABRIC	S.Y.	5,926.000 X		=		
AR156520	INLET PROTECTION	EACH	2.000 X		=		
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	L.F.	2,567.000 X		=		
AR201663	SAND MIX CRACK REPAIR	L.F.	4,856.000 X		=		
AR209605	CRUSHED AGG. BASE COURSE - 5"	S.Y.	4,855.000 X		=		
AR209606	CRUSHED AGG. BASE COURSE - 6"	S.Y.	798.000 X		=		
AR209607	CRUSHED AGG. BASE COURSE - 7"	S.Y.	3,894.000 X		=		
AR209609	CRUSHED AGG. BASE COURSE-9"	S.Y.	1,113.000 X		=		
AR209612	CRUSHED AGG. BASE COURSE - 12"	S.Y.	122.000 X		=		
AR302611	ASPHALT TREATED PERMEABLE SUBBASE	S.Y.	4,855.000 X		=		
AR302630	ATPS TEST SECTION	EACH	1.000 X		=		
AR401613	BIT. SURF. CSE.-METHOD I, SUPERPA	TON	2,093.000 X		=		
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	3,511.000 X		=		

WAUKEGAN NATIONAL
LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - WA071

ECMS002 DTGECM03 ECMR003 PAGE 3
RUN DATE - 07/06/16
RUN TIME - 223326

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR401660	SAW & SEAL BIT. JOINTS	L.F.	1,060.000	X	=		
AR401665	BITUMINOUS PAVEMENT SAWING	L.F.	1,977.000	X	=		
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	774.000	X	=		
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	573.000	X	=		
AR403614	BIT. BASE CSE.-METHOD II, SUPERPA	TON	3,116.000	X	=		
AR403630	BITUMINOUS BASE TEST SECTION	EACH	1.000	X	=		
AR501514	14" PCC PAVEMENT	S.Y.	4,733.000	X	=		
AR501530	PCC TEST BATCH	EACH	1.000	X	=		
AR501665	PCC PAVEMENT SAWING	L.F.	561.000	X	=		
AR501900	REMOVE PCC PAVEMENT	S.Y.	6,404.000	X	=		
AR602510	BITUMINOUS PRIME COAT	GAL.	3,234.000	X	=		
AR603510	BITUMINOUS TACK COAT	GAL.	4,552.000	X	=		
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	6,197.000	X	=		
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	6,799.000	X	=		
AR620530	PAVEMENT MARKING-EPOXY	S.F.	2,717.000	X	=		

WAUKEGAN NATIONAL
LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - WA071

ECMS002 DTGECM03 ECMR003 PAGE 4
RUN DATE - 07/06/16
RUN TIME - 223326

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR620590	TEMPORARY MARKING	S.F.	2,882.000 X		=		
AR620900	PAVEMENT MARKING REMOVAL	S.F.	1,629.000 X		=		
AR701512	12" RCP, CLASS IV	L.F.	115.000 X		=		
AR705506	6" PERFORATED UNDERDRAIN	L.F.	5,113.000 X		=		
AR705630	UNDERDRAIN INSPECTION HOLE	EACH	9.000 X		=		
AR705640	UNDERDRAIN CLEANOUT	EACH	13.000 X		=		
AR705903	REMOVE UNDERDRAIN INSP. HOLE	EACH	7.000 X		=		
AR705904	REMOVE UNDERDRAIN CLEANOUT	EACH	2.000 X		=		
AR705943	ADJUST UNDERDRAIN INSP. HOLE	EACH	2.000 X		=		
AR705944	ADJUST UNDERDRAIN CLEANOUT	EACH	2.000 X		=		
AR751411	INLET-TYPE A	EACH	1.000 X		=		
AR751540	MANHOLE 4'	EACH	1.000 X		=		
AR751900	REMOVE INLET	EACH	1.000 X		=		
AR751943	ADJUST MANHOLE	EACH	2.000 X		=		
AR800938	CRACK CONTROL OVERLAY MATERIAL 85	S.Y.	1,319.000 X		=		

WAUKEGAN NATIONAL
LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - WA071

ECMS002 DTGECM03 ECMR003 PAGE 5
RUN DATE - 07/06/16
RUN TIME - 223326

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR800939	CRACK CONTROL REPAIR MATERIAL 850	S.Y.	1,415.000 X			=	
AR800954	4" SECONDARY UNDERDRAIN	L.F.	451.000 X			=	
AR800971	GRANULAR DRAINAGE SUBBASE - 8"	S.Y.	5,926.000 X			=	
AR800972	BITUMINOUS SAND MIX - 2"	S.Y.	787.000 X			=	
AR803011	RELOCATE LIGHTED SIGN	EACH	2.000 X			=	
AR803012	RELOCATE UNLIGHTED SIGN	EACH	6.000 X			=	
AR901510	SEEDING	ACRE	3.400 X			=	
AR905510	TOPSOILING (FROM ON SITE)	C.Y.	1,138.000 X			=	
AR908510	MULCHING	ACRE	3.400 X			=	
TOTAL						\$	

NOTE:

1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.



WAUKEGAN NATIONAL AIRPORT
WAUKEGAN PORT DISTRICT
2601 Plane Rest Drive
Waukegan, Illinois 60087
Telephone: 847.244.0055
Fax: 847.244.3813

SUMMARY OF QUANTITIES

INDEX OF SHEETS	
SHEET NO.	TITLE
1	COVER SHEET
2	SHEET INDEX AND SUMMARY OF QUANTITIES
3	SITE PLAN, SAFETY PLAN & GENERAL NOTES
4	CONSTRUCTION SAFETY NOTES & DETAILS
5-11	PHASING PLANS
12	ALIGNMENT DATA
13-14	TYPICAL SECTIONS & PAVEMENT DETAILS
15-17	SWPP PLANS
18-19	SWPPP DETAILS
20-23	REMOVAL PLANS
24	MILLING PLAN - TAXIWAY C NORTH
25-31	CRACK REPAIR PLANS
32-43	PLAN AND PROFILES
44-63	CROSS SECTIONS
64-69	GRADING PLANS
70	JOINTING PLAN - TAXIWAY B SOUTH
71	JOINTING DETAILS
72	STAKING PLAN - TAXIWAY B SOUTH
73	DRAINAGE SCHEDULES
74	DRAINAGE DETAILS
75	UNDERDRAIN DETAILS
76-79	ELECTRICAL PLANS
80	LIGHT & SIGN SCHEDULE
81-91	ELECTRICAL DETAILS
92-96	MARKING PLANS
97-98	LANDSCAPING PLANS
99	BORING LOCATION MAP
100-103	BORING LOGS

ITEM NO.	DESCRIPTION	UNIT	AS BID QUANTITY	RECORD PAID
AR108158	1/C #8 5KV UG CABLE IN UD	LINEAR FOOT	7,879.0	
AR108960	REMOVE CABLE	LINEAR FOOT	2,737.0	
AR110504	4-WAY CONCRETE ENCASED DUCT	LINEAR FOOT	59.0	
AR110551	EXTEND DUCT	LINEAR FOOT	124.0	
AR110900	REMOVE DUCT	LINEAR FOOT	60.0	
AR125410	MITL-STAKE MOUNTED	EACH	43.0	
AR125415	MITL-BASE MOUNTED	EACH	11.0	
AR125565	SPLICE CAN	EACH	2.0	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	52.0	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	7.0	
AR125906	REMOVE SPLICE CAN	EACH	1.0	
AR125941	ADJUST STAKE MOUNTED LIGHT	EACH	10.0	
AR125942	ADJUST BASE MOUNTED LIGHT	EACH	2.0	
AR150510	ENGINEER'S FIELD OFFICE	LUMP SUM	1.0	
AR150530	TRAFFIC MAINTENANCE	LUMP SUM	1.0	
AR152410	UNCLASSIFIED EXCAVATION	CUBIC YARD	4,514.0	
AR156510	SILT FENCE	LINEAR FOOT	880.0	
AR156513	SEPARATION FABRIC	SQUARE YARD	5,926.0	
AR156520	INLET PROTECTION	EACH	2.0	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	LINEAR FOOT	2,567.0	
AR201663	SAND MIX CRACK REPAIR	LINEAR FOOT	4,856.0	
AR209605	CRUSHED AGG. BASE COURSE - 5"	SQUARE YARD	4,855.0	
AR209606	CRUSHED AGG. BASE COURSE - 6"	SQUARE YARD	798.0	
AR209607	CRUSHED AGG. BASE COURSE - 7"	SQUARE YARD	3,894.0	
AR209609	CRUSHED AGG. BASE COURSE - 9"	SQUARE YARD	1,113.0	
AR209612	CRUSHED AGG. BASE COURSE - 12"	SQUARE YARD	122.0	
AR302611	ASPHALT TREATED PERMEABLE SUBBASE	SQUARE YARD	4,855.0	
AR302630	ATPS TEST SECTION	EACH	1.0	
AR401613	BIT. SURF. CSE.-METHOD I, SUPERPAVE	TON	2,093.0	
AR401650	BITUMINOUS PAVEMENT MILLING	SQUARE YARD	3,511.0	
AR401660	SAW & SEAL BIT. JOINTS	LINEAR FOOT	1,060.0	
AR401665	BITUMINOUS PAVEMENT SAWING	LINEAR FOOT	1,977.0	
AR401900	REMOVE BITUMINOUS PAVEMENT	SQUARE YARD	774.0	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	SQUARE YARD	573.0	
AR403614	BIT. BASE CSE.-METHOD II, SUPERPAVE	TON	3,116.0	

ITEM NO.	DESCRIPTION	UNIT	AS BID QUANTITY	RECORD PAID
AR403630	BITUMINOUS BASE TEST SECTION	EACH	1.0	
AR501514	14" PCC PAVEMENT	SQUARE YARD	4,733.0	
AR501530	PCC TEST BATCH	EACH	1.0	
AR501665	PCC PAVEMENT SAWING	LINEAR FOOT	561.0	
AR501900	REMOVE PCC PAVEMENT	SQUARE YARD	6,404.0	
AR602510	BITUMINOUS PRIME COAT	GALLONS	3,234.0	
AR603510	BITUMINOUS TACK COAT	GALLONS	4,552.0	
AR620520	PAVEMENT MARKING-WATERBORNE	SQUARE FOOT	6,197.0	
AR620525	PAVEMENT MARKING-BLACK BORDER	SQUARE FOOT	6,799.0	
AR620530	PAVEMENT MARKING-EPOXY	SQUARE FOOT	2,717.0	
AR620590	TEMPORARY MARKING	SQUARE FOOT	2,882.0	
AR620900	PAVEMENT MARKING REMOVAL	SQUARE FOOT	1,629.0	
AR701512	12" RCP, CLASS IV	LINEAR FOOT	115.0	
AR705506	6" PERFORATED UNDERDRAIN	LINEAR FOOT	5,113.0	
AR705630	UNDERDRAIN INSPECTION HOLE	EACH	9.0	
AR705640	UNDERDRAIN CLEANOUT	EACH	13.0	
AR705903	REMOVE UNDERDRAIN INSPECTION HOLE	EACH	7.0	
AR705904	REMOVE UNDERDRAIN CLEANOUT	EACH	2.0	
AR705943	ADJUST UNDERDRAIN INSPECTION HOLE	EACH	2.0	
AR705944	ADJUST UNDERDRAIN CLEANOUT	EACH	2.0	
AR751411	INLET-TYPE A	EACH	1.0	
AR751540	MANHOLE 4'	EACH	1.0	
AR751900	REMOVE INLET	EACH	1.0	
AR751943	ADJUST MANHOLE	EACH	2.0	
AR800938	CRACK CONTROL OVERLAY MATERIAL (8501)	SQUARE YARD	1,319.0	
AR800939	CRACK CONTROL REPAIR MATERIAL (8502)	SQUARE YARD	1,415.0	
AR800954	4" SECONDARY UNDERDRAIN	LINEAR FOOT	451.0	
AR800971	GRANULAR DRAINAGE SUBBASE - 8"	SQUARE YARD	5,926.0	
AR800972	BITUMINOUS SAND MIX - 2"	SQUARE YARD	787.0	
AR803011	RELOCATE LIGHTED SIGN	EACH	2.0	
AR803012	RELOCATE UNLIGHTED SIGN	EACH	6.0	
AR901510	SEEDING	ACRE	3.4	
AR905510	TOPSOILING (FROM ON SITE)	CUBIC YARD	1,138.0	
AR908510	MULCHING	ACRE	3.4	

REHABILITATE
PORTIONS OF
TAXIWAYS B & C,
PHASE 2

IDA No: UGN-4521
SBG No: 3-17-SBGP-TBD

Contract No: WA071

NO.	DATE	DESCRIPTION			
		DES	DWN	REV	
A	7/20/16	Revise Pay Item	LDH	LDH	RMH

ISSUE: July 29, 2016
PROJECT NO: 16A0013
CAD FILE: 02-SOQ.DWG
DESIGN BY: KMS 06/06/2016
DRAWN BY: KMS 06/06/2016
REVIEWED BY: LDH 6/9/2016

© Copyright Hanson Professional Services Inc. 2013
SHEET TITLE

SHEET INDEX
AND SUMMARY
OF QUANTITIES

PAYMENT WILL BE MADE UNDER THE ITEM NUMBERS, DESCRIPTIONS AND UNITS NOTED IN THE ABOVE TABLE IN ACCORDANCE WITH THE BASIS OF PAYMENT FOR EACH RESPECTIVE WORK ITEM NOTED IN THE SPECIAL PROVISIONS, COMPLETED AND ACCEPTED BY THE ENGINEER.

BASIS OF PAYMENT

125-5.1 Add the following:

"Payment will be made at the Contract unit price for each complete airfield light fixture installed, taxi guidance sign relocated, and/or splice can installed in place by the Contractor and accepted by the Engineer. This price shall be full compensation for furnishing all materials and for all preparation, assembly, and installation of these materials; and for all excavation, backfilling, and restoration; and for all labor, testing, equipment, tools, and incidentals necessary to complete this item.

"Removal work will be paid for at the contract unit bid price per each for the respective airfield light fixture removal, and/or splice can removal. Said price and payment shall constitute full compensation for field verification of existing site conditions and power sources, disconnecting the respective power sources, removing the respective airfield light or sign, with associated mounting stakes, bases, foundations, handholes, splice cans, and transformers; for all excavating, backfilling, and restoration; for furnishing all earth material; and for furnishing all coordination, labor, tools, equipment, and incidentals necessary to complete this item of work.

"Payment will be made under:

"Item AR125410	MITL - Stake Mounted - per each.
Item AR125415	MITL - Base Mounted - per each.
Item AR125565	Splice Can - per each.
Item AR125901	Remove Stake Mounted Light - per each.
Item AR125902	Remove Base Mounted Light - per each.
Item AR125906	Remove Splice Can - per each.
Item AR125941	Adjust Stake Mounted Light - per each.
Item AR125942	Adjust Base Mounted Light - per each.
Item AR803011	Relocate Lighted Sign - per each.
Item AR803012	Relocate Unlighted Sign - per each."

