


NOTES:

- SEE SHEET RL-1 FOR ELECTRICAL SYMBOL LIST, ABBREVIATIONS, AND GENERAL NOTES.
- 2. FIXTURE SHALL BE MOUNTED AT 12'-0" AFF ON HEADWALL.
- 3. 1/2" DIA. RGSC AND 4" RADIUS ELBOW FOR EACH CEILING MOUNTED LUMINAIRE SHALL BE FURNISHED AND INSTALLED BY THE PRECAST CONCRETE BOX MANUFACTURER. THE COST OF THIS WORK SHALL BE INCLUDED IN THE PRECAST CONCRETE BOX SEGMENTS PAY ITEM. SEPARATE PAYMENT WILL NOT BE MADE.
- 4. VERIFY LUMINAIRE DIMENSIONS WITH THE LIGHT FIXTURE SHOP DRAWINGS PRIOR TO THE CONSTRUCTION OF PRECAST CONCRETE BOX SEGMENTS.





PVC COATED CONDUIT CLAMP DETAIL

5	0	5	10	15	20	25
Ĭ						
		SC	CALE IN FE	ET		

TOTAL SHEE SHEETS NO. SECTION DEERFIELD AD PEDESTRIAN UNDERPASS DESIGNED JLW REVISED USER NAME = JMiddlet LE NAME LAKE 08-00083-00-BT STATE OF ILLINOIS 1257 СЈМ REVISED LIGHTING PLAN & DETAILS CONTRACT NO. 63450 DEPARTMENT OF TRANSPORTATION KMY REVISED CHECKED PLOT SCALE = 1:60 TO STA. FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT SHEETS STA. REVISED DATE 04/09/10