SUMMARY OF QUANTITIES

SPECIALTY ITEM (*)	S.P. NEEDED (X)	PAY ITEM NUMBER	FULL PAY ITEM NAME	UNIT OF MEASURE	QUANTITY (Y047)
	Х	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT		
		550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	8
	***************************************	330A0030	STORWI SEVVERS, CLASS A, TTPE 1, 12	FOOT	-
*		56400100	FIRE HYDRANTS TO BE MOVED	EACH	1
*	3	5040000		54011	
	X	56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1
	Х	60238800	INLETS, TYPE A	EACH	1
		60250200	CATCH BASINS TO BE ADJUSTED	EACH	1
		60255500	MANHOLES TO BE ADJUSTED	EACH	1
		60265700	VALVE VAULTS TO BE ADJUSTED	EACH	4
		60402210	GRATES, TYPE 8	EACH	1
	3	00402210	GRAIES, ITPE 0	EACH	3
*		60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1
	Magazia	67100100	MOBILIZATION	L SUM	1
		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LSUM	1
		70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1
		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
	,	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
	X	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1.50
		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	499
*		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	840
*		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	27
	× X	78300100	PAVEMENT MARKING REMOVAL	SQ FT	218
	· · · · · · · · · · · · · · · · · · ·			3. 74	<u>, , , , , , , , , , , , , , , , , , , </u>
	Х	XX007657	TRAIL TREE ROOT BARRIER	FOOT	684
	X	Z0013798	CONSTRUCTION LAYOUT	LSUM	1
		<u> </u>	SCHEDULE OF EARTH EXCAVATION (20200100)	1	

* DENOTES SPECIALTY ITEM.

SCHEDULE OF EARTH EXCAVATION (20200100)													
LOCATION	EARTH	EXCAVATION	EMBANKMENT	BALANCE		REMOVAL AND	SUB-BASE						
· · · · · · · · · · · · · · · · · · ·		EXCAVATION	AVAILABLE	VOLUME	PER STAGE		DISPOSAL OF	GRANULAR					
		20200100		NEEDED	WASTE (+)		UNSUITABLE	MATERIAL,					
			ADJUSTED FOR		NEED (-)		MATERIAL	TYPE B 6"					
			SHRINKAGE				20201200	31101400					
		CU YD	CU YD	CU YD	CU YD		CU YD	SQ YD					
MADISON ST. BIKE PATH - STA. 9+97.09 TO STA. 19+74.81	238	202	30	172		130	1,321						
	PROJECT TOTAL	238					130	1,321					
(ASSUMES 15% SHRINKAGE FACTOR)								3					
SEE CROSS-SECT	ION SHEETS 15	5-24 FOR S	STATION BY	STATION	BREAKDOW	N OF EA	RTHWORK QU	ANTITY					

USER NAME = \$USER\$ DESIGNED - CRC REVISED -\$FILEL\$ DRAWN - ML

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.U. RTE. 2674 MADISON STREET (CH 8) BIKE PATH IMPROVEMENTS SUMMARY OF QUANTITIES SHEET NO. 2 OF 2 SHEETS STA. TO STA.

SECTION COUNTY TOTAL SHEET NO.

07-00001-10-BT DUPAGE 24 4

SUMMARY OF QUANTITIES CONTRACT NO: 63470 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

REVISED PLOT SCALE = \$SCALE\$ CHECKED - MPK REVISED REVISED