SCHEDULE OF QUANTITIES

28100201 STONE RIPRAP, CLASS A1

			LENGTH	WIDTH	
	STATION	OFFSET	(FOOT	(FOOT)	(TON
LT	338+61	0' LT - 26' LT	15.5	26.0	27.0
RT	338+61	0' RT - 25' RT	15.5	25.0	26.0
				TOTAL =	53.0
			_	USE =	55.0

35102000 AGGREGATE BASE COURSE, TYPE B, 8 INCH

AREA	WIDTH	LENGTH				
(SQ YD)	(FOOT)	(FOOT	STATION	TO	STATION	
97.8	4.0	220.0	339+71		337+51	LT
97.8	4.0	220.0	339+71		337+51	RT
195.6	TOTAL =					
200.0	USF =					

54020802 PRE-CAST BOX CULVERT 8 X 2 (M273)

STATION		(FOOT)
338+61.00	SN 010-8135	40.0
	TOTAL =	40.0
	USE =	40.0

54001001 BOX CULVERT END SECTION, CULVERT 1

	STATION		(EACH)
LT	338+61.00	SN 010-8135	1.0
RT	338+61.00	SN 010-8135	1.0
-		TOTAL =	2.0
		USE =	2.0

51500100 NAME PLATES

(EACH		STATION	
1.0	SN 010-8135	338+61.00	RT
1.0	TOTAL =		
1.0	USE =		

61101016 STORM SEWERS, CLA, PROTECTED, 14"

STATION

;	338+71	LOCATION TO BE DETERMINED BY ENGINEER DURING CONSTRUCTION	80.0
		TOTAL =	80.0
		USE =	80.0

(FOOT)

61133200 FIELD TILE JUNCTION VAULT, 3' DIA

STATION		(EACH
338+71	LOCATIONS TO BE DETERMINED BY ENGINEER DURING CONSTRUCTION	2.0
	TOTAL =	2.0
	USE =	2.0

XX005655 STORM SEWER REMOVAL, UNDER 18"

(FOOT)		STATION
80.0	LOCATION TO BE DETERMINED BY ENGINEER DURING CONSTRUCTION	338+71
80.0	TOTAL =	
80 O	IISE =	

FILE NAME =	USER NAME = blackrt	DESIGNED	-	RTB	REVISED	-	RTB
c:\pw_work\PWIDOT\BLACKRT\d0132092\D570	701-sht-Schedule.dgn	DRAWN	-	JJB	REVISED	-	
	PLOT SCALE = 40.0000 '/ IN.	CHECKED	-		REVISED	-	
	PLOT DATE = 3/30/2010	DATE	-	3-3-2009	REVISED	-	

	F.A.S. RTE.				TOTAL SHEETS	SHEET NO.					
SCHEDULE OF QUANTITIES							2	ICR	CHAMPAIGN	29	8
									CONTRACT	NO	70701
SCALE: N/A	FED. RO	AD DIST. NO.	ILLINOIS FED. AI	D PROJECT							