

July 12, 2021

SUBJECT FAS Route 220 (IL 94) Project STP-DY2E(975) Section (23-BR)BJR,BP,BRR Mercer County Contract No. 68F78 Item No. 32, July 30, 2021 Letting Addendum A

# NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised page i of the Table of Contents to the Special Provisions
- 2. Revised page 4 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

CLEG

Jack A. Elston, P.E. Bureau Chief, Design and Environment

FAS Route 220 (IL 94) Project STP-DY2E(975) Section (23-BR)BJR,BP,BRR Mercer County Contract No. 68F78

# TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
LOCATION OF UNDERGROUND STATE MAINTAINED FACILITIES	2
SEEDING, MINOR AREAS	2
SLOPE WALL SLURRY PUMPING	3
GUARDRAIL AGGREGATE EROSION CONTROL	3
TRAFFIC BARRIER TERMINALS	4
TRAFFIC CONTROL PLAN	4
LANE CLOSURE RESTRICTIONS	4
WIDTH RESTRICTION SIGNING	5
TEMPORARY CONCRETE BARRIER REFLECTORS	7
PCC SUPERSTRUCTURE AGGREGATE OPTIMIZATION	7
AGGREGATE QUALITY	8
PCC QC/QA ELECTRONIC REPORTS SUBMITTAL	8
PCC AUTOMATIC BATCHING EQUIPMENT	8
STONE RIPRAP, CLASS B4 (SPECIAL)	9
JACK AND REMOVE EXISTING BEARINGS	9
CLEANING AND PAINTING EXISTING STEEL STRUCTURES	10
CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	31
STRUCTURAL REPAIR OF CONCRETE	55
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)	
COMPENSABLE DELAY COSTS (BDE)	65
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	68
DISPOSAL FEES (BDE)	77
MOBILIZATION (BDE)	78
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE)	78
PORTLAND CEMENT CONCRETE BRIDGE DECK CURING (BDE)	79
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	80
SILT FENCE, INLET FILTERS, GROUND STABILIZATION AND RIPRAP FILTER FABRIC (BDE	90 (
STEEL COST ADJUSTMENT (BDE)	95
STEEL PLATE BEAM GUARDRAIL MANUFACTURING (BDE)	97
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	98
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	98
Revised 7/12/2	2021

## **TRAFFIC BARRIER TERMINALS**

Effective February 1, 1996 Revised November 5, 2004

Widening of existing shoulders/slopes for the construction of Traffic Barrier Terminals shall be completed as directed by the Engineer and paid for as specified in Article 109.04 of the Standard Specifications.

### TRAFFIC CONTROL PLAN

Effective: May 4, 2021

Traffic control shall be in accordance with the applicable sections of the "Standard Specifications for Road and Bridge Construction," the applicable guidelines contained in the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways," these Special Provisions, and any special details and Highway Standards contained herein and in the plans.

Special attention is called to Section 701 and Articles 107.09 and 107.14 of the "Standard Specifications for Road and Bridge Construction" and the following Highway Standards relating to traffic control:

701001	701006	701011	701106	701201
701301	701311	701321	701901	704001

Six (6) width restriction signs shall be needed. There location will be discussed at the Pre-Construction meeting.

Traffic Control and Protection Standard 701321: Temporary pavement markings shown in the standard shall be Pavement Marking Tape, Type III according to Article 1095.06 of the Standard Specifications. Placement and removal of temporary pavement markings shown on the standard shall not be paid for separately but shall be included in the cost of the TRAFFIC CONTROL AND PROTECTION, STANDARD 701321.

### LANE CLOSURE RESTRICTIONS

No lane closures shall be permitted from November 24th to April 1st unless approved by the Engineer.

Revised 7/12/2021