## ROUTE: US 14 (Northwest Hwy.) from IL 22 to 1/2 Mile East of IL 22

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
L 22	1/2 Mile East of IL 22	EB	1	12	6	72	8
	(East of Lake County Line)	EB	2	12	6	72	8
· · · · · · · · · · · · · · · · · · ·		EB	1	12	6	72	8
		EB	2	12	15	180	20
		EB	1	12	6	72	-8
′		EB	2	12	15	180	20
		EB	1	12	6	72	8
······		EB	2	12	6	72	8
		EB	1 1	12	6	72	8
		EB	2	12	8	96	11
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		WB	1 1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
······································		WB	2	12	6	72	8
			<del>}</del>			72	
•		WB	1	12	6		8
		WB	2	12	6	72 72	8 8
		WB	1	12 12	6	72	
······································		WB	2		6		8
		WB	1	12	6	72	8
		WB	2	12	6	72 70	8
		WB	1 1	12	6	72	8
		WB ·	2	12	6	72	8
		WB	1	12	6 .	72 70	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
,		WB	1	12	- 6	72	8
·		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	11	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	6	72	8 ·

TOTALS:

284 FT 379 SY

ı	FILE NAME =	USER NAME = wilgreendp	DESIGNED -	REVISED -
I	c:\pw_work\PWIDOT\WILGREENDP\dØ125047\C	esign,dgn	DRAWN -	REVISED -
ı		PLOT SCALE = 100.0000 '/ IN.	CHECKED -	REVISED -
ı		PLOT DATE = 5/18/2009	DATE -	REVISED -

PATCHING SCHEDULE US 14		F.A. SECTION		COUNTY	TOTAL SHEETS	SHE	
			VAR.	2009-057PCC-PP	LK. & MCH.	23	14
					CONTRACT	NO. 6	<b>50H4</b>
SHEET NO. OF SHEET	S STA.	TO STA.	FED. ROA	AD DIST. NO. 1   ILLINOIS FED. AI	D PROJECT		