

– I wo component nonstaining
gray sealing compound with
polysulfide liquid polymer
gun-grade with primer.

*(18	18, 19	19, 1	919	9.15) I-	11		6	2983
FED. R	oad dis	ĩ. NO,	1	ILLINOIS	FED.	AID	PROJECT	Г
STA.				ΤO	STA.			
90/94		٠			C00I	к	45	35
RTE.	5	ECH	ION		COUN	IY	SHEETS	NO.

## NOTES:

- 1. Reinforcement bar shall conform to the requirements of AASHTO M-31 or M-322 Grade 60.
- 2. Concrete: f'c = 3500 psi
- 3. Fluted knee wall shall be paid for per foot as "Fluted Knee Wall." Included in the cost of "Fluted Knee Wall" shall be "Concrete Superstructures" (stem). "Concrete Structures" (foundation), reinforcement bars (epoxy coated), rustication finish for fluted knee walls, protective coat, expansion joint filler and sealing compound.
- 4. At locations where Fluted Knee Wall abuts a rigid structure, a  $l_2$ " thick preformed expansion joint filler (PJF) conforming to the shape of the structure shall be installed between the wall and the structure,  $\frac{3}{4}$ " PJF shall be installed where Fluted Knee Wall footing abuts curb and gutter. The cost shall be included in "Fluted Knee Wall".
- 5. Quantities shown in "Bill of Material" are for one (1) foot of "Fluted Knee Wall".
- 6. Chain Link Fence will not be paid for in this Contract, but shall be furnished and installed in Contract 60B88.
- 7. Unless noted otherwise, Protective Coat shall be applied according to Section 503.19 of the Standard Specifications to the top of stem and to the face of stem and top of footing on the Frontage Road side of the Knee Wall.
- 8. Minimum lap length for #4 bars shall be 1'-8".

		-
REVISIONS NAME		
 NAME	DATE	
		71

## LEGEND:



Chain Link Fabric Rustication Finish Earth

Sheet SL of 7

Concrete

SIONS	DATE	ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
		71ST ST TO 63RD ST (NORTHBOUND KNEE WALLS)
·		FLUTED KNEE WALL STANDARD DETAILS
		SCALE: None DRAWN BY: CHD
		DATE: JANUARY 14, 2009 CHECKED BY: MJP