



EXISTING TOPOGRAPHY

FAP 347 06-000071-00-SW COOK

TE-00D1(773)

ILLINOIS PROJECT

VILLAGE SECTION

CONTRACT NO. 63183

LIGHTING GENERAL NOTES

- 1. ALL LIGHTING UNITS SHALL BE LABELED AS DIRECTED BY THE ENGINEER. LIGHTING UNIT NUMBERING SHALL BE AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
- 2. CONTRACTOR SHALL BE RESPONSIBLE TO COORDINATE ELECTRICAL WORK WITH OTHER TRADES.
- 3. AFTER UNIT DUCT IS INSTALLED, FOUNDATION RACEWAYS SHALL BE FILLED WITH FINE AGGREGATE ACCORDING TO ARTICLE 836.03. A STAINLESS STEEL SCREEN SHALL BE INSTALLED TO SEAL THE OPENING BELOW THE POLE BASE FROM RODENT ENTRY.
- 4. ALL THREADS OF BOLTS SHALL BE COATED WITH A NON-LEAD BASED ANTI-SIEZE COMPOUND PRIOR TO ASSEMBLY.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE JULIE NUMBER IS 811. A MINIMUM OF FORTY- EIGHT (48) HOURS ADVANCE NOTICE ID REQUIRED.

MEMBERS OF JULIE KNOWN TO BE WITHIN THE LIMITS OF IMPROVEMENT: ROOSEVELT ROAD (FAP 347) FROM MANNHEIM ROAD TO WESTCHESTER BOULEVARD

- COMMONWEALTH EDISON
- NICOR
- VILLAGE OF WESTCHESTER
- AMERITECH
- ILLINOIS DEPARTMENT OF TRANSPORTATION



