

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	12R - 4	WILL	199	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

80% FED. 20% STATE  
 50% STATE 31.5% MOKENA 12.5% FRANKFORT  
 75% MOKENA 25% FRANKFORT  
 50% STATE 50% MOKENA

CODE #	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				ROADWAY I000-1A	SIGNALS Y031-1F	FIRE HYDRANT Y060	DETOUR I000-1A	BIKE PATH Y046
40701956	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"	SQ YD	22913	22913				
42001300	PROTECTIVE COAT	SQ YD	4957	4957				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	432	432				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	14268	14268				
42400800	DETECTABLE WARNINGS	SQ FT	490	490				
44000100	PAVEMENT REMOVAL	SQ YD	19,742	19,742				
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	506	506				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3277	3277				
44000300	CURB REMOVAL	FOOT	362	362				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3437	3437				
44000600	SIDEWALK REMOVAL	SQ FT	796	796				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	12	12				
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	148	148				
44003800	MEDIAN SURFACE REMOVAL	SQ FT	479	479				
44004250	PAVED SHOULDER REMOVAL	SQ YD	884	884				
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	21	21				
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	38	38				
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	135	135				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	115	115				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	281	281				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1				
50104300	CONCRETE HEADWALL REMOVAL	CU YD	1.3	1.3				
50105220	PIPE CULVERT REMOVAL	FOOT	439	439				
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	87	87				
5421A015	PIPE CULVERTS, CLASS A, TYPE 1 15" (TEMPORARY)	FOOT	106	106				
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2				
54213672	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 27"	EACH	1	1				
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1				
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1				
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	1	1				
54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	1	1				
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	2	2				
54247140	GRATING FOR CONCRETE FLARED END SECTION 27"	EACH	1	1				
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1				
54247180	GRATING FOR CONCRETE FLARED END SECTION 42"	EACH	1	1				
54248150	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	1	1				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	241	241				

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION  SUMMARY OF QUANTITIES U.S. RTE. 30 (LINCOLN HIGHWAY)  SCALE : 1" = 50' DATE : 03/21/2008 DRAWN BY : BAE CHECKED BY : GB
NAME	DATE	

DLZ