

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	12R - 4	WILL	199	9
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE #	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				ROADWAY 1000-1A	SIGNALS Y031-1F	FIRE HYDRANT Y060	DETOUR I000-1A	BIKE PATH Y046
X0301834	STORM SEWER TO BE FILLED	FOOT	237	237				
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	289	289				
X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	128	128				
X0322089	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	125	125				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8				
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48				
X0322125	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	164	164				
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	1667					1667
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1325		1325			
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	6287	6287				
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	6287	6287				
* X0324007	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1		1			
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	7458	7458				
X0325837	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 6 INCH	FOOT	179	179				
X0325840	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH	FOOT	210	210				
X0712400	TEMPORARY PAVEMENT	SQ YD	3175	3175				
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	9	9				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	919	919				
X6020097	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 1 FRAME, OPEN LID, RESTRICTOR PLATE	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12				
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1			
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	962		962			
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1139		1139			
* X8900040	MODIFY TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1			
* XX003660	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM24F SM12F	FOOT	1325		1325			
XX004592	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2				
XX005630	TEMPORARY AGGREGATE SHOULDER	TON	745	745				
XX005656	INLET FILTER CLEANING	EACH	188	188				
XX006661	UNINTERRUPTABLE POWER SUPPLY	EACH	1		1			
20076600	TRAINEES	HOURL	3000	3000				
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	29213	29213				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
X0326140	STORM SEWER REMOVAL 2"	FOOT	24	24				
35600730	HOT-MIX ASPHALT BASE COURSE WIDENING, 13 1/2"	SQ YD	49	49				
X0326139	TEMPORARY TRAFFIC SIGNAL, WOOD POLE	EACH	1		1			
* X0326136	FULL-ACTUATED CONTROLLER AND CABINET (SPECIAL)	EACH	1		1			
* X0326137	STEEL COMBINATION MAST ARM LOWER ASSEMBLY AND POLE 34 FT.	EACH	1		1			
* X0326138	STEEL COMBINATION MAST ARM LOWER ASSEMBLY AND POLE 36 FT.	EACH	1		1			
* X0326141	STEEL COMBINATION MAST ARM LOWER ASSEMBLY AND POLE 50 FT.	EACH	2		2			

@ Y080
* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES U.S. RTE. 30 (LINCOLN HIGHWAY)
NAME	DATE	
		SCALE : 1" = 50' DATE : 03/21/2008 DRAWN BY : BAE CHECKED BY : GB

Rev.