

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	12R - 4	WILL	199	20
STA.		TO STA.		
FED. ROAD DIST. NO.		BALANCE	FED. AID PROJECT	

PAVEMENT MARKING SCHEDULE

LOCATION		THERMOPLASTIC PAVEMENT MARKING						POLYUREA PAVEMENT MARKING				RAISED REFL PAVT MKR	RAISED REF PVT MK REM	PAVT MARKING REMOVAL	SHORT TERM PAVT MKING
ROAD	STATION	LETTERS AND SYMBOLS SQ FT	LINE 4" FOOT	LINE 6" FOOT	LINE 8" FOOT	LINE 12" FOOT	LINE 24" FOOT	LETTERS AND SYMBOLS SQ FT	TYPE I - LINE 4" FOOT	TYPE I - LINE 6" FOOT	TYPE I - LINE 12" FOOT	EACH	EACH	SQ FT	FOOT
U. S. RTE. 30	275+00 - 290+00	182.0	3751	619		75	15					56	49	3823	264
	290+00 - 303+00	291.2	6377	575	1089	540	51					120	96	3958	479
	303+00 - 318+00	364.0	4880	1960	1393	1806	229					158	126	5777	493
	318+00 - 331+00	109.2	1161	363		204	56					22	18	1151	80
	SUBTOTAL =	946.4	16169	3517	2482	2625	351	0	0	0	0	356	289	14709	1316
WOLF RD.	294+00 - 297+50	182.0	1213	647			40					53	42	887	121
	302+50 - 309+00		61	49			0	145.6	4283	185	112	58	46	1520	192
	SUBTOTAL =	182.0	1274	696	0	0	40	145.6	4283	185	112	111	88	2407	313
TOTAL		1128.4	17442	4213	2482	2625	391	145.6	4283	185	112	467	377	17116	1629

STAGING SCHEDULE

LOCATION		WORK ZONE PAVT MK REM SQ FT	EPOXY PAVEMENT MARKING					WET RF TEM TAPE T3 4	WET RF TEM TAPE T3 6	WET RF TEM TAPE T3 12	TEMP PAVEMENT SQ YD	TEMP ACCESS-COM ENT EACH	TEMP AGGREGATE SHLD TON
ROAD	STATION		PVT MK LTR-SYM SQ FT	PVT MK LINE 4 FOOT	PVT MK LINE 6 FOOT	PVT MK LINE 12 FOOT	PVT MK LINE 24 FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	TON
U. S. RTE. 30	275+00 - 290+00		109.2	9458	575	453	14				85	1	40
	290+00 - 303+00			17663		574					273	4	177
	303+00 - 318+00	92	364.0	23840	1387	810	334	279			2857	4	616
	318+00 - 331+00		72.8	2835	621	126	47				1		5
	SUBTOTAL =	92	546.0	53796	2583	1963	395	279	0	0	3216	9	839
WOLF RD.	294+00 - 297+50	1408		265				3940					
	302+50 - 309+00	1104		260				3239	179	210	6		5
	SUBTOTAL =	2512	0	525	0	0	0	7179	179	210	6	0	5
TOTAL		2604	546.0	54321	2583	1963	395	7458	179	210	3222	9	844

EROSION CONTROL SCHEDULE

LOCATION		TEMPORARY EROSION CONTROL SEEDING POUND	TEMPORARY DITCH CHECKS EACH	INLET AND PIPE PROTECTION EACH	INLET FILTERS EACH	SEDIMENT CONTROL SILT FENCE FOOT	SEDIMENT CONTROL SILT FENCE MAINTENANCE FOOT	INLET FILTER CLEANING EACH
U. S. RTE. 30	275+00 - 290+00	3	0	1	0	419	419	
	290+00 - 303+00	121.8	12	9	38	2380	2380	76
	303+00 - 318+00	245	17	15	55	3064	3064	110
	318+00 - 331+00	22.7	0	2	0	213	213	0
	SUBTOTAL =	392.5	29	27	93	6076	6076	186
WOLF RD.	294+00 - 297+50		0	0	0	174	174	
	302+50 - 309+00	11.7	0	0	0	37	37	
	SUBTOTAL =	11.7	0	0	0	211	211	0
TOTAL		404	29	27	93	6287	6287	186

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>SCHEDULE OF QUANTITIES</p> <p>U.S. RTE. 30 (LINCOLN HIGHWAY)</p> <p>SCALE : 1" = 50' DRAWN BY : BAE</p> <p>DATE : 03/21/2008 CHECKED BY : GB</p>