

NOTES:

- 1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
- 2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION

- 1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
- 2. REMOVE AND REPLACE FULL DEPTH PATCHES
- 3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = smithkl	DESIGNED - R. SHAH	REVISED - A. ABBAS 01-20-98		PAVEMENT PATCHING FOR	RTE. SECTION COUNTY SHEETS NO.
Wi\distatd\22x34\bd22.dgn		DRAWN -	REVISED - A. ABBAS 04-27-98	STATE OF ILLINOIS		1300 2008 - 017 RS COOK 24 13
	PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED - R. BORO 01-01-07	DEPARTMENT OF TRANSPORTATION	HMA SURFACED PAVEMENT	BD400-04 (BD-22) CONTRACT NO. 60E45
	PLDT DATE = 5/21/2008	DATE - 10-25-94	REVISED - R. BORO 09-04-07		SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT