INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1.	TITLE SHEET
2.	INDEX OF SHEETS, STATE STANDARDS, GENERAL NOTES
3.	SUMMARY OF QUANTITIES
4.	EXISTING TYPICAL SECTIONS
5.	PROPOSED TYPICAL SECTIONS
6-8.	ROADWAY AND PAVEMENT MARKING PLAN
9.	LOOP DETECTOR PLANS
10.	DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING
11.	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT
12.	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT
13.	BUTT JOINT AND HMA TAPER DETAILS
14.	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
15.	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)
16.	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
17.	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)
18.	PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING
19.	ARTERIAL ROAD INFORMATION SIGN
20.	DRIVEWAY ENTRANCE SIGNING
21.	DISTRICT 1 DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING

STATE STANDARDS

STANDAR	D NO.	DESCRIPTION
00000	01- <i>05</i>	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
44220	01-03	CLASS C AND D PATCHES
60400	06- <i>03</i>	FRAME AND GRATE, TYPE 3
60405	51-02	FRAME AND GRATE, TYPE 11
6060	01-03	CONCRETE CURB TYPE B AND COMBINATION CONRETE CURB AND GUTTER
70160	6-05	URBAN LANE CLOSURE, 2W WITH MOUNTABLE MEDIAN
70170	01-05	URBAN LANE CLOSURE, MULTILANE INTERSECTION
70190	01	TRAFFIC CONTROL DEVICES

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL *J.U.L.I.E.* AT (800)892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED.)
- ALL PAVEMENT MARKING SHALL BE PLACED THROUGHOUT THE PROJECT ACCORDING TO DISTRICT 1 TYPICAL PAVEMENT MARKING.
- 3. ALL HMA PAVEMENT PATCHING SHALL BE CLASS D.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT
- 5. ANY PAVEMENT MARKINGS AND RAISED REFLECTIVE PAVEMENT MARKERS OBLITERATED BY MILLING AND RESURFACING OPERATIONS ON SIDE STREETS AND ENTRANCES SHALL BE REPLACED AND PAID FOR IN KIND.
- 6. BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD (FOR FUTURE REFERENCES), ALL EXISTING PAVEMENT MARKING LINES IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL STRIPING SHALL BE AS DIRECTED BY THE ENGINEER.
- 7. ALL PAVEMENT PATCHING AND CURB & GUTTER REMOVAL AND REPLACEMENT LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- 8. DRAINAGE STRUCTURE ADJUSTMENT OR RECONSTRUCTION LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- 9. LOCATIONS FOR TYPE 3 GRATES TO REPLACE EXISTING NON-BICYCLE-SAFE GRATES AND REPLACEMENT OF BROKEN TYPE 11 FRAMES AND GRATES WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- 10. FRAMES AND GRATES ADJUSTMENT OF PRIVATE UTILITIES WITHIN THE LIMITS OF THE IMPROVEMENTS SHALL BE DONE BY THEIR RESPECTIVE OWNERS AND ARE NOT PART OF THIS CONTRACT.
- 11. THE RESIDENT ENGINEER SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

- 12. THE ENGINEER SHALL CONTACT MS. DEBBIE HANLON, THE TRAFFIC FIELD ENGINEER, @ 847-438-2300 TWO (2) WEEKS PRIOR TO THE START OF THIS PROJECT SO THAT EXACT STATIONING OF NO PASSING ZONES AND OTHER PERMANENT PAVEMENT MARKINGS MAY BE ESTABLISHED.
- 13. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
- 14. EXISTING BROKEN FRAMES AND LIDS, OR NON-BICYCLE-SAFE GRATES SHALL
 BE REMOVED AND DISPOSED OF BY THE CONTRACTOR AND SHALL BE REPLACED
 AS DIRECTED BY THE ENGINEER. REPLACEMENT FRAMES AND GRATES OR LIDS
 WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04 OF THE STANDARD
 SPECIFICATIONS, UNLESS A SEPARATE PAY ITEM HAS BEEN PROVIDED.
- 15. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS
- 16. DOUBLE LANE MARKERS ARE TO BE USED AS SHOWN ON THE DISTRICT ONE DETAIL FOR TYPICAL APPLICATION OF RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) SHOWN IN THE PLANS.
- 17. WHEN ARTIFICIAL LIGHTING IS USED IN NIGHT OPERATIONS THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.
- 8. WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED 1½INCHES (40 MM) WHERE THE SPEED LIMIT IS 45 MPH (80 KM/H) OR LESS AND 1 INCH (25 MM) WHERE THE SPEED LIMIT IS GREATER THAN 45 MPH (80 KM/H). WITH WRITTEN APPROVAL FROM THE ENGINEER, A MAXIMUM GRADE DIFFERENTIAL OF 3 INCHES (75 MM) MAY BE ALLOWED IF THE EDGE OF THE MILLING IS SLOPED A MINIMUM 1:3 (V:H)
- 19. BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF ALL RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT), IN ACCORDANCE WITH THE "BUTT JOINT AND HOT-MIX ASPHALT TAPER DETAILS" SHEET INCLUDED IN THE PLANS, UNLESS OTHERWISE SPECIFIED.
- 20. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIA'S.
- 21. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, AND WITH THE CITY OF WAUKEGAN.
- 22. REMOVAL AND REPLACEMENT OF UNSUITABLE SUB-BASE MATERIAL AT PAVEMENT PATCHING LOCATIONS SHALL BE PAID FOR AS FOLLOWS:

REMOVAL AND REPLACEMENT 4" OR LESS SHALL BE INCLUDED IN THE COST OF PATCHES OF THE CLASS & TYPE BEING PLACED.

REMOVAL AND REPLACEMENT IN THE EXCESS OF 4" WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.

= X/14/2008 = X/1225568\Cvul\Sheeta\11225568_NOTES. = 11 = mhuska = Defoult

ringroup

Excellence through Ownership

 DESIGNED DRAWN
 WJV
 REVISED

 200 West Front Street Wheaton, II 60187
 CHECKED DATE
 BLB
 REVISED

 DATE
 5/23/08
 REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 137 (GREENWOOD AVE. – BLANCHARD RD.)
INDEX OF SHEETS, STATE STANDARDS, AND GENEERAL NOTES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

A Rev. 7-16-08

_	FΔP			ΤΩΤΔΙ	SHEET
	RTE.	SECTION	COUNTY	SHEETS	NO.
	352	(E, M, D) RS-6	LAKE	21	2
			CONTRACT	NO. 6	0E56
	FED. I	OAD DIST. NO. 1 ILLINOIS FED. A	AID PROJECT		

215