ROUTE: IL RTE 132 (GRAND AVENUE) - FROM U.S. ROUTE 45 TO IL ROUTE 59

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
U.S 45		WB	2	12	6	72	8
		WB	2	4	10	40	4
		WB	2	4	10	40	4
		C/L	C/L	2	150	225	25
		WB	2	6	10	60	7
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	1	6	12	72	8
		EB	2	12	10	120	13
		EB	1	4	12	48	5
		EB	2	4	6	24	3
	SAND LAKE ROAD	EB	2	4	6	24	3
SAND LAKE ROAD		WB	1	12	15	180	20
		CL	1	3	10	30	3
		WB	2	4	15	60	7
		WB	1	12	8	96	11
		WB	1	12	8	96	11
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		EB	2	6	10	60	7
		EB	1	4	25	100	11
		CL	CL	2	50	75	8
		EB	2	6	12	72	8
		EB	1	6	12	72	8
		EB	2	6	12	72	8
		EB	1	6	12	72	8
		EB	2	6	12	72	8
		EB	1	6	12	72	8
	DEEP LAKE ROAD	EB	2	6	12	72	8
DEEP LAKE ROAD		CL	CL	2	24	36	4
		WB	1	12	40	480	53
		WB	2	12	40	480	53
		WB	1	12	60	720	80
		CL	CL	3	30	90	10
		WB	2	12	100	1200	133
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	15	180	20
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
	IL RTE 83	CL	CL	3	100	300	33

ROUTE: IL RTE 132 (GRAND AVENUE) - FROM U.S. ROUTE 45 TO IL ROUTE 59

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
DEEP LAKE ROAD		CL	CL	3	300	900	100
		CL	CL	3	200	600	67
		CL	CL	3	200	600	67
		EB	1	6	12	72	8
		EB	2	6	12	72	8
		EB	2	6	12	72	8
		CL	CL	3	200	600	67
		EB	1	12	20	240	27
		EB	1	6	12	72	8
		EB	1	6	12	72	8
		EB	1	6	12	72	8
		EB	1	6	12	72	8
		EB	1	6	12	72	8
	IL RTE 83	EB	1	6	12	72	8
IL RTE 83		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	1	6	10	60	7
		WB	1	6	10	60	7
		WB	1	6	12	72	8
		WB	1	6	12	72	8
		WB	1	6	12	72	8
		WB	1	6	12	72	8
		WB	1	6	20	120	13
		WB	1	6	20	120	13
		WB	1	6	20	120	13
		WB	1	6	20	120	13
		WB	1	6	20	120	13
		EB	2	10	12	120	13
		EB	1	6	12	72	8
		EB	1	6	12	72	8
		EB	1	6	12	72	8
		EB	1	6	12	72	8
		EB	1	6	30	180	20
		EB	1	4	20	80	9
		EB	1	4	20	80	9
		EB	1	12	15	180	20
		EB	1	6	12	72	8
		EB	1	6	12	72	8
		EB	1	6	12	72	8
	FAIRFIELD ROAD	EB	1	6	12	72	8
FAIRFIELD ROAD		WB	1	12	10	120	13
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	1	4	10	40	4
		EB	1	12	12	144	16
		EB	1	6	12	72	8
		EB	1	6	12	72	8
		EB	1	6	12	72	8
	IL. RTE 59	EB	1	6	12	72	8
		TOTALS:			2509		1545 SY

FILE NAME = c:\projects\d136008\design_aa.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 6/26/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 132

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-047 RS	LAKE	41	16
		CONTRACT NO. 60E96		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

...\projects\d136008\design_aa.dgn 6/26/2008 4:54:45 PM User=wilgreendp