



ITEM NO.	ITEMS	UNIT	URBAN QUANTITY	ROADWAY		CULVERTS	LANDSCAPING	RETAINING WALLS	TRAFFIC SIGNALS						EMERGENCY VEHICLE PREEMPTION		RIGHT TURN LN (STA. 3167+50 TO STA. 3177+30)	SIDEWALK	
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	IL RT 59 @ BLACK ROAD	IL RT 59 @ VERTIN BLVD	IL RT 59 @ STA. 3122+00 LEFT	IL RT 59 @ THEODORE ST	IL RT 59 @ VERMETTE CIRCLE	IL RT 59 @ CATON FARM ROAD	INTERCONNECT	100% SHOREWOOD	100% JOLIET	100% JOLIET	50% STATE 50% SHOREWOOD	50% STATE 50% JOLIET
				J000-2A	X028-2A	Y003	Y007	80% FED 10% STATE 5% SHOREWOOD 5% WILL COUNTY	100% SHOREWOOD	100% JOLIET	80% FED 10% STATE 10% JOLIET	80% FED 10% STATE 10% JOLIET	80% FED 10% STATE 5% JOLIET 5% WILL COUNTY	80% FED 20% STATE	Y031-3D	J000-1A	SFTY-1B		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2,023	2,023															
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,067	1,067															
20101000	TEMPORARY FENCE	FOOT	2,976	2,976															
20101100	TREE TRUNK PROTECTION	EACH	80	80															
20101200	TREE ROOT PRUNING	EACH	80	80															
20200100	EARTH EXCAVATION	CU YD	14,915	14,915															
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	17,847	17,847															
20400800	FURNISHED EXCAVATION	CU YD	91,104	91,104															
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1,184				1,184												
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	14,153	14,153															
20800150	TRENCH BACKFILL	CU YD	22,098	22,098															
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	4,267	4,267															
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	23,006	23,006															
21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	41,810	41,810															
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	7,541	7,541															
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	2,959	2,959															
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	200	200															
25000210	SEEDING, CLASS 2A	ACRE	4.50	4.50															
25000310	SEEDING, CLASS 4	ACRE	0.75	0.75															
25000322	SEEDING, CLASS 5A	ACRE	0.75	0.75															
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,134	1,134															
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,134	1,134															
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,134	1,134															
25000775	SELECTIVE MOWING STAKES	EACH	6	6															
25003310	INTERSEEDING, CLASS 4	ACRE	0.75	0.75															
25100115	MULCH, METHOD 2	ACRE	15.25	15.25															
25100630	EROSION CONTROL BLANKET	SQ YD	28,024	28,024															
25200110	SODDING, SALT TOLERANT	SQ YD	47,857	47,857															
25200200	SUPPLEMENTAL WATERING	UNIT	2,441	2,441															
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	3,229	3,229.0															
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,514	1,514															
28000500	INLET AND PIPE PROTECTION	EACH	236	236															
28000510	INLET FILTERS	EACH	410	410															
28001000	AGGREGATE (EROSION CONTROL)	TON	23	23															
28100107	STONE RIPRAP, CLASS A4	SQ YD	600		180		420												
28200200	FILTER FABRIC	SQ YD	665		240		425												
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	28,900	28,900															
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	109	108															
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	2,538	2,538															
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,857	1,857															
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,295	1,295															
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	127,370	120,830												548			
42001300	PROTECTIVE COAT	SQ YD	77,337	77,337															
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	266	266															

* SPECIALITY ITEM
 ** 100% SHOREWOOD QUANTITIES (NOT IDENTIFIED IN FUNDING BREAKDOWNS NOTED ABOVE)

REVISIONS	
NAME	DATE
REVISED IL59 ALIGN.	12/22/06

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 ILLINOIS ROUTE 59
 DATE 3/18/08
 DRAWN BY FA
 CHECKED BY RCB
 SCALE: NONE

DATE: _____ BY: _____
 PLAN: _____
 NOTE: BOOK _____
 CITY OF JAY, ILLINOIS
 PROJECT NO. _____

DATE: _____ BY: _____
 PROJECT: ILLINOIS ROUTE 59
 STATE: ILLINOIS
 COUNTY: WILL
 PROJECT NO. _____