

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	114R-1	WILL	355	18
STA.	TO STA.		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

DRIVEWAY SCHEDULE

LOCATION	PCC DRV PVMT 6"	PCC DRV PVMT 8"	HOT-MIX ASPHALT SURF CSE, MIX "C" N50, 2"	HOT-MIX ASPHALT BSE CSE, 6"	HOT-MIX ASPHALT BSE CSE, 8"	COMB CONC C&G TY M-6.06	CONC CURB TY B
	SQ YD	SQ YD	TONS	SQ YD	SQ YD	FOOT	FOOT
IL ROUTE 59							
STA 3032+50 LT			10.6		95	78	54
STA 3035+40 LT			24.5		219		148
STA 3044+40 LT			8.4	75			
STA 3044+75 LT	66						
STA 3045+99 LT	113						
STA 3050+66 LT			3.8	34			
STA 3053+90 LT	41						
STA 3055+40 LT	46						
STA 3056+60 RT			14.4		129		64
STA 3058+88 RT			8.1		72		64
STA 3060+30 RT			12.1		108		66
STA 3063+10 RT			13.8		123		69
STA 3065+07 RT			8.5		76	30	66
STA 3067+50 RT			29.3		262		136
STA 3079+12 RT			14.3		127		78
STA 3084+27 RT			22.1		198		103
STA 3085+40 LT			9.7		86		51
STA 3093+66 LT			20.2		180		75
STA 3105+95 LT			29.9		267		135
STA 3111+15 LT			22.2		198		62
STA 3114+10 LT			18.6		166		61
STA 3115+71 LT			26.1		233		62
STA 3127+89 RT		174					86
STA 3131+84 RT		77					44
STA 3166+58 LT		155					90
STA 3178+27 LT		133					60
STA 3178+24 RT		235					122
STA 3184+94 LT		237					84
STA 3185+07 RT		180					117
STA 3185+50 TO STA 3187+10 LT							162
			998.1				
TOTALS	266	1189	1295	109	2538	108	2059

EARTHWORK SCHEDULE

1 LOCATION	2 EARTH EXCAVATION	3 ROCK EXCAVATION	4 REMOVAL AND DISPOSAL OF UNSUITABLE OR UNSTABLE MATERIAL	5 EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	6 EMBANKMENT	7 EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) FURNISHED EXCAVATION
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
IL RTE 59 (US RTE 52 -- BLACK RD) STAGE I STA 3032+25.84 to STA 3082+28.00	2,774	0	6,257	2,358	12,611	-10,253
IL RTE 59 (BLACK RD -- THEODORE ST) STAGE I STA 3082+28.00 to STA 3135+16.41	980	0	1,347	833	24,720	-23,887
IL RTE 59 (THEODORE ST -- CATON FARM RD) STAGE I STA 3135+16.41 to STA 3193+25.00	4,061	0	2,151	3,452	7,009	-3,558
SUB. TOTAL STAGE I	7,815	0	9,755	6,643	44,341	-37,698
IL RTE 59 (US RTE 52 -- BLACK RD) STAGE II STA 3032+25.84 to STA 3082+28.00	5,111	0	5,168	4,345	6,864	-2,519
IL RTE 59 (BLACK RD -- THEODORE ST) STAGE II STA 3082+28.00 to STA 3135+16.41	761	0	1,353	647	28,025	-27,379
IL RTE 59 (THEODORE ST -- CATON FARM RD) STAGE II STA 3135+16.41 to STA 3193+25.00	986	0	1,570	838	11,733	-10,895
SUB. TOTAL STAGE II	6,858	0	8,091	5,829	46,622	-40,793
THEODORE ST STA 94+87 to STA 106+08	242	0	0	206	141	65
GRAND TOTAL	14,915	0	17,847	12,678	91,104	-78,426

SHRINKAGE FACTORS: EARTH EXCAVATION: 15% (ASSUMED) ROCK EXCAVATION: 0% (ASSUMED)

NOTE: TOPSOIL REMOVAL AND UNDERCUT PAID FOR AS REMOVAL OF UNSUITABLE MATERIAL

POROUS GRANULAR EMBANKMENT SUBGRADE (PGES)

LOCATION	VOLUME CU YDS
IL ROUTE 59	
STAGE 1	6733
STAGE 2	6133
SUB TOTAL	12867
10% *	1287
TOTAL	14153

*10% ADDED FOR MISCELLANEOUS AREAS DETERMINED BY THE ENGINEER

REVISIONS	
NAME	DATE
REVISED IL59 ALIGN.	12/22/06

ILLINOIS DEPARTMENT OF TRANSPORTATION

DRIVEWAY, EARTHWORK, AND PGES SCHEDULES

DATE: 3/18/08
DRAWN BY: MJG
CHECKED BY: VJD

SCALE: NONE

DATE	
BT	
NO. OF SHEETS	
NO. OF THIS SHEET	
DATE	
NO.	

DATE	
BT	
NO. OF SHEETS	
NO. OF THIS SHEET	
DATE	
NO.	