

F.A.I.	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
94/90	8		соок	25	14
STA.		Т	O STA.		
FED. ROA	D DIST. NO.	ILLING	DIS FED. A	ID PROJECT	-
6298	8				

DETAIL A REINFORCEMENT SCHEDULE AND BILL OF MATERIAL

Bar	No.	Size	Length	Shape
h(E)	8	#4	9'-8"	
n(E)	11	#6	5′-6″	L
n1(E)	11	#5	5′-10″	L
w(E)	4	#4	9'-8"	
		1		
	Item	Unit	Qty.	
Concr Struct		Cu. Yd.	<u>1</u> .4	
Concr Super	ete structur	Cu. Yd.	1.4	
Reinfo Epoxy	coated	Pound	240	
Rustic	ation F.	Sq. Ft.	19	
Protec	ctive Co	Sq. Yd.	7	

NOTES:

- 1. All stations and offsets measured from S. La Salle St. B.
- Back Face is face adjacent to Frontage Rd, and Front Face is face adjacent to Expressway,
- 3. Concrete: f'c = 3500 psi
- Provide California Finish on top of foundation between stem and Frontage Road. See Roadway Details.
- 5. At locations where Fluted Knee Wall abuts a rigid Structure, a 2" thick Preformed Expansion Joint Filler conforming to the shape of the Structure shall be installed between the Fluted Knee Wall and the Structure.
- Apply Protective Coat to top and back face of stem and top of Frontage Road side of foundation.
- 7. For Fluted Knee Wall standard details, see Sheet SD-1
- Existing Curb, Curb & 8. B.F. = Back Face (Frontage Road Side) Gutter to remain F.F. = Front Face (Expressway Side) E.F. = Each Face
 - Shape finished grade as required to match existing conditions.
 - 10. P.J.F. included in cost of concrete structures.

SHEET SD-2 REVISION ILLINOIS DEPARTMENT OF TRANSPORTATION DATE F.A.I. 94/90 (DAN RYAN EXPRESSWAY) 🗟 NORTHBOUND KNEE WALLS (47TH ST TO 45TH ST) DETAILS A & B SCALE: NTS DRAWN BY: TL DATE: 04/25/08 CHECKED BY: BLU

-1/2" P.J.F.