SUMMARY OF QUANTITIES

| | | | | 100% STATE | |
|------------|--|--------|----------|---------------|--|
| CODE NO. | ITEM | UNIT | QUANTITY | Jood | |
| 20200100 | EARTH EXCAVATION | CU YD | 108 | 108 | |
| 21101645 | TOPSOIL FURNISH AND PLACE, 12" | SQ YD | 114 | 114 | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 6 | 6 | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 6 | 6 | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | | | 6 | |
| 25001800 | SEEDING, CLASS 4 (MODIFIED) | ACRE | 0.06 | 0.06 | |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 273 | 273 | |
| 44004250 | PAVED SHOULDER REMOVAL | SQ YD | 84 | 84 | |
| 50300225 | CONCRETE STRUCTURES | CU YD | 9,4 | 9.4 | |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 8.2 | 8.2 | |
| 50300300 | PROTECTIVE COAT | SQ YD | 41 | 41 | |
| 50300510 | RUSTICATION FINISH | SQ FT | 88 | 88 | |
| (50800205) | REINFORCEMENT BARS, EPOXY COATED | POUND | 1,780 | 1,78 | |
| 66400550 | CHAIN LINK FENCE, 4' (SPECIAL) | FOOT | 515 | 515 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70101800 | TRAFFIC CONTROL AND PROTECTION,(SPECIAL) | L SUM | 1 | 1 | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 6 | 6 | |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 26 | 26 | |
| X0323973 | SEDIMENT CONTROL, SILT FENCE | FOOT | 515 | 515 | |
| X0323974 | SEDIMENT CONTROL, SILT FENCE MAINTENANCE | FOOT | 129 | 129 | |
| X0324640 | FLUTED KNEE WALL | FOOT | 425 | 425 | |
| X2500322 | SEEDING, CLASS 5A,(MODIFIED) | ACRE | 0.06 | 0.06 | |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

| F.A.I. | SECTION | COUNTY | TOTAL | SHEET NO. |
|---------|------------------|---------------|---------|--------------|
| 94/90 | * | соок | 27 | 3 |
| STA. | | TO STA. | | |
| FED. RO | AD DIST, NO. ILL | NOIS FED. AID | PROJECT | |

62990

INDEX OF SHEETS

DESCRIPTION

SHEET

| 1 | COVER SHEET |
|-------|---|
| 2 | GENERAL NOTES AND PROJECT COMMITMENTS |
| 3 | SUMMARY OF QUANTITIES / INDEX / HIGHWAY STANDARDS |
| 4 | EXISTING AND PROPOSED TYPICAL SECTIONS |
| 5-9 | ALIGNMENT PLANS, SURVEY TIES AND CONTROL POINTS |
| 10-12 | EXISTING AND PROPOSED KNEE WALL PLANS |
| 13-15 | STRUCTURAL DETAILS |
| 16 | BD-51 DISTRICT 1, BENCHING DETAIL FOR EMBANKMENT WIDENING |
| 17 | TC-10 DISTRICT 1, TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS & DRIVEWAYS |
| 18 | TC-17 DISTRICT 1, TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES PARTIAL RAMP CLOSURES |
| 19 | TC-18 DISTRICT 1, SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS |
| 20 | TC-22 DISTRICT 1, ARTERIAL ROAD INFORMATION SIGN |
| 21-27 | CROSS SECTIONS |
| | |

IDOT HIGHWAY STANDARDS

| 1001 HIOHWAY STANDANDS | | |
|------------------------|-------------------|---|
| | SHEET | DESCRIPTION |
| | 000001-05 | STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS |
| | 001001-01 | AREAS OF REINFORCEMENT BARS |
| | 001006 | DECIMAL OF AN INCH AND OF A FOOT |
| | 664001 <i>-01</i> | CHAIN LINK FENCE |
| | 701601- 05 | URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN |
| | 701701- 05 | URBAN LANE CLOSURE, MULTILANE INTERSECTION |
| | 701801- 03 | LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE, for speeds < 45 mph |
| | 701901 | TRAFFIC CONTROL DEVICES |
| | 720001 | SIGN PANEL MOUNTING DETAILS |
| | 720006 -01 | SIGN PANEL ERECTION DETAILS |
| | 728001 | TELESCOPING STEEL SIGN SUPPORT |
| | 731001 | BASE FOR TELESCOPING STEEL SIGN SUPPORT |
| | | |

SOQ-1

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
NORTHBOUND KNEE WALLS (43RD ST TO ROOT ST)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 04/25/08

DRAWN BY: JDC CHECKED BY:

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
112 228 0100
www.bbandainc.com

A Rev. 7-18-08