

SECTION COUNTY KANE N/A 06-00017-00-PV 232 117 STA. TO STA. FED. ROAD DIST. NO. \_ ILLINOIS FED. AID PROJECT


## NOTES:

## GROUNDING SYSTEM

- THE GROUNDING SYSTEM SHALL CONSIST OF AN INSULATED CONDUCTOR TYPE XLP, NO. 6 A.W.G., STRANDED COPPER TO BE INSTALLED IN RACEWAYS. THE GROUNDING CABLE SHALL BE INSTALLED IN A CONTINUOUS MANNER AS SHOWN ON THE CABLE PLAN PROVIDED. ALL GROUNDING CONDUCTORS SHALL BE BONDED TO METAL ENCLOSURE (HANDHOLE, POST, MAST ARM, CONTROLLER, ETC.). GROUND ROD SHALL BE 3/4" DIA. x 10'-0" (20mm x 3.0m) LONG, COPPER CLAD. ONE GROUND ROD SHALL BE INSTALLED AT ALL POST FOUNDATIONS, POLE FOUNDATIONS, CONTROLLER CABINET FOUNDATION AND ELECTRICAL SERVICE INSTALLATION AS INDICATED ON THE CABLE PLAN. IF THERE ARE ANY SPECIAL CONDITIONS SUCH AS SUB-SURFACE CONDITIONS OR INSTALLATION PROBLEMS, THE RESIDENT ENGINEER SHALL BE NOTIFIED OR CONTACT THE BUREAU OF TRAFFIC, ILLINOIS DEPARTMENT OF TRANSPORTATION DISTRICT ONE AT (847) 705-4139.
- 2. THE NEUTRAL CONDUCTOR AND THE GROUND CONDUCTOR SHALL BE CONNECTED IN THE SERVICE INSTALLATION. AT NO OTHER POINT IN THE TRAFFIC SIGNAL SYSTEM SHALL THE NEUTRAL AND GROUND CONDUCTORS BE CONNECTED.
- 3. ALL EQUIPMENT GROUNDING CONDUCTORS SHALL TERMINATE AT THE GROUND BUS IN THE CONTROLLER CABINET.
- 4. THE CONTRACTOR SHALL PROVIDE A GROUND CABLE WITH CONNECTORS BETWEEN THE HANDHOLE COVER AND HANDHOLE FRAME.








3/4" (20mm) HEAVY-DUTY GROUND ROD CLAMP (BURNDY TYPE GRC OR APPROVED EQUAL)

## NOTES:

- $\circ$  ALL CLAMPS SHALL BE BRONZE OR COPPER, UL APPROVED.
- GROUND CABLE SHALL BE LOOPED OVER HOOKS IN THE HANDHOLES
   6.5' (2.0m) SLACK SHALL BE PROVIDED IN SINGLE HANDHOLES 13' (4.0m) OF SLACK SHALL BE PROVIDED IN DOUBLE HANDHOLES. 5' (1.4m) OF SLACK SHALL BE PROVIDED BETWEEN FRAME AND COVER.



EXISTING HANDHOLE COVER + FRAME - GROUNDING DETAIL (NOT TO SCALE)


REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE -	
		DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS
		·

DRAWN BY: KKP

CHECKED BY: TVW

SCALE: NTS

DATE: 05/16/08



## ELECTRICAL SERVICE - PANEL DIAGRAM (TYPICAL FOR POLE AND GROUND MOUNTED SERVICE)

(413 mm)<sub>6.25</sub>"


(0.29 m)

CABINET - BASE BOLT PATTERN

ANCHOR BOLT LOCATIONS

CABINET BASE

(37 mm)



TRAFFIC SIGNAL CONTROLLER (50mm) GALV. CONDUIT


\_3/4" x 10' (20mm x 3.0m) COPPER

CLAD GROUND ROD

HANDHOLE COVER + FRAME - GROUNDING DETAIL

SEE DETAIL "A"

(NOT TO SCALE)



-SEE DETAIL "B"

MAST ARM POLE / POST-GROUNDING DETAIL

(NOT TO SCALE)



FINISH GRADE

2" (50mm) GALV. CONDUIT

SERVICE INSTALLATION

GROUND MOUNT

(NOT TO SCALE)

SURVETED
PLOTTED
ALIGNMENT CHECKED
RT. OF WAY CHECKED
CADD FILE NAME