SECTION 17, TOWNSHIP 35, RANGE 14 SECTION 18, TOWNSHIP 35, RANGE 14

	SUMMARY OF QUANTITIES					PAVEMENT MARKINGS SIGNS LANDSCAPE LIGHTS SIGNALS TRAINING CONSTRUCTION TYPE CODE					
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	1000	SFTY-1D	Y002-1C			Y031	Y080
-	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10						
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10						
	25000500	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10						
	25200110	SODDING, SALT TOLERANT	SQ YD	100	100						
	35800200	AGGREGATE BASE REPAIR	TON	150	150						
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3370	3370				:g		
	40600300	AGGREGATE (PRIME COAT)	TON	100	100						
	40600895	CONSTRUCTION TEST STRIP	EACH	2	2						
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	400	400				-		
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2800	2800						
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT , 6" INCH	SQ YD	180	180						
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQ FT	1680	1680						
	42400800	DETECTABLE WARNINGS	SQ FT	300	300						
	44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	33700	33700						1.00
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1730	1730		* 1 *			:	
	44000600	SIDEWALK REMOVAL	SQ FT	1680	1680						
	44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	80	80						
	44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	110	110						
	44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	710	710						
	44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	33700	33700						
	60200105	CATCH BASINS, TYPE A, 4'- DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	5	5						
	60223800	MANHOLES, TYPE A 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1						
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	29	29						
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	11	11						
	60255500	MANHOLES TO BE ADJUSTED	EACH	15	15						
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	4						
	60300205	FRAMES AND GRATES TO BE ADJUSTED, (SPECIAL)	EACH	2	2						
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1730	1730						
	67100100	MOBILIZATION	L SUM	1	1						
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1_						
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1						
·.	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LSUM	1_	1						
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	111						
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	660	660						
*	78000100	THERMOPLASTIC PAVEMENT MARKING — LETTERS AND SYMBOLS	SQ FT	170		170					
*	78000200	THERMOPLASTIC PAVEMENT MARKING — LINE 4"	FOOT	13500		13500					
*	78000400	THERMOPLASTIC PAVEMENT MARKING — LINE 6"	FOOT	660		660					
*	78000600	THERMOPLASTIC PAVEMENT MARKING LINE 12"	FOOT	1650		1650					
*	78000650	THERMOPLASTIC PAVEMENT MARKING — LINE 24"	FOOT	310		310					
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	40	40						
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	180	180						
	60500040	REMOVING MANHOLES	EACH	1	1						
	60500050	REMOVING CATCH BASINS	EACH	5	5				- 2		
	X0322752	WORK ZONE PAVEMENT MARKING REMOVAL	FOOT	660	660						100 0 0 00
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2800	2800						
	X7200400	WORK ZONE PUBLIC INFORMATION SIGNS	EACH	2	2						
Ш	XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	500	500						

* - INDICATES SPECIALTY ITEMS

F. A. U. RTE.	SECTION		COUNTY	TOTAL SHEETS	SHEET HO			
2859	08-00222-00	-RS	соок	018	002			
STA.	TO STA.							
FED. R	OAD DIST. NO.	- BLLINOIS FED. AID PROJECT						

CONTRACT #63045

GENERAL NOTES:

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- 2. UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- 4. SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- 5. ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- 6. THE NOMINAL THICKNESS OF HOT-MIX ASPHALT MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARTIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS SURFACE IS PLACED.

ILLINOIS DEPARTMENT OF TRANSPORTATION

REVISIONS NAME ASHLAND AVENUE STREET RESURFACING SUMMARY OF QUANTITIES AND GENERAL NOTES SCALE: VERT. NA DRAWN BY NO CHECKED BY RES POSITION MEMORY SOUTH HOLDING ALGOE SEND (PRO) SEND MEMORY SOUTH HOLDING ALGOE SEND (PRO) SUBMIT HORS DESCRIPTION NO. 184001189.