
TYPICAL SECTION

STA 89+25 TO 92+00



BITUMINOUS APPLICATION RATES

SURFACE MIXTURES: 119 LB/SY-IN
OTHER BITUMINOUS MIXTURES: 112 LB/SY-IN
BITUMINOUS MATERIAL (PRIME COAT): 0.000286 TON/SY
AGGREGATE (PRIME COAT): 0.0015 TON/SY

* MAINTAIN EXISTING X-SLOPE X-SLOPE DESIRED 3/16 "/FT. MINIMUM 1/8 "/FT.

* D2 SPRING PATCHING 2007-2

| FILE NAME = | USER NAME = grantpm | DESIGNED ~ | REVISED - | | TYPICAL SECTIONS | | | | | F.A.I. | SECTION | COUNTY TOTAL SHEET | |
|-----------------------|--------------------------------------|------------|-----------|------------------------------|------------------|-----------|----|--------|------|---------|-------------------|--------------------|------------------|
| P:\1-80 resurfovr.dgn | | DRAWN - | REVISED - | STATE OF ILLINOIS | | | | | | | 80 | * | ROCK ISLAND 31 7 |
| | PLOT SCALE = 50.000 ' / IN. | CHECKED - | REVISED - | DEPARTMENT OF TRANSPORTATION | | | | | | | | CONTRACT NO. 64D34 | |
| | PLOT DATE = Thu May 15 11:03:28 2008 | DATE - | REVISED - | | SCALE: | SHEET NO. | OF | SHEETS | STA. | TO STA. | FED. ROAD DIST. N | LLINOIS FED | AID PROJECT |