# **GENERAL NOTES**

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then. use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslope, and beyond the toe of front slope on fill sections without ditches. This workwill be included in the contract unit price.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of MOBILIZATION.

Mulch Method II shall be applied over all seeded areas. This stall be included in the cost of the MOBILIZATION

Install a "TO ACTIVATE SIGNAL" sign for the traffic signal detector loops. The detail of this sign is included in the plans. This work will be included in the cost of TRAFFIC CONTROL AND PROTECTION STANDARD 701316.

At bridge expansion joints, if temporary expansion joint bulkheads are attached to adjacent deck slabs or abutments for support, the Contractor shall cut the attachments as soon as the concrete has set to prevent joint damage due to horizontal contraction or expansion.

The Contractor shall sandblast the top of the beams upon removal of the bridge deck. This work will be included in the cost of CONCRETE REMOVAL.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Mediacom - Moline Gallatin River Communications - Galesburg Commonwealth Edison Company - Rockford Verizon - Sycamore Jo-Carroll Energy - Elizabeth NICOR Gas Co. - Naperville Frontier/Citizens - Lanark Insight Communications - Rockford

## **INDEX OF SHEETS**

1. Cover Sheet 2. Summary of Quantities

- 3. General Notes
- 4. Traffic Control Plan SN 008-0028
- 5, -6, Traffic Control Plan SN 071-0069 7, -8, Traffic Control Plan SN 089-0060
- 9. Traffic Control and Protection for Ramps

#### Structure Number 008-0028

- General Plan & Elevation
  Existing Deck Plan & Cross Section
  Existing Deck Plan & Cross Section
  Joint Details
  Joint Details
  Preformed Joint Strip Seal
- 16. Bar Splicer Assembly Details

### Structure Number 071-0069

General Plan & Elevation
 Existing Deck Plan & Cross Section
 Joint Details
 Preformed Joint Strip Seal
 Bar Splicer Assembly Details

Structure Number 089-0060

22. General Plan & Elevation
 23. Existing Deck Plan and Cross Section
 24. Joint Details
 25. Preformed Joint Strip Seal
 26. Bar Splicer Assembly Details

## STANDARDS

701201-02 Lane Closure, 2L, 2W, Day Only, for Speeds > 45 MPH 701321-09 Lane Closure, 2L, 2W, Bridge Repair with Barrier 701400-02 Approach to Lane Closure, Freeway/Expressway 701401-04 Lane Closure, Freeway/Expressway 701901 Traffic Control Devices 704001-04 Temporary Concrete Barrier

FILE NAME =	USER NAME = linkdj	DESIGNED -	REVISED -						
O:\BR\CADD plans\Various Counties\Contra	ct #54099 2008 expansion joints\0080028.dgm	DRAWN -	REVISED -	STATE OF ILLINOIS			4 w		
	PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION					
	PLOT DATE = Sat Mar 15 11:20:55 2008	DATE -	REVISED -		SCALE:	SHEET NO.	ÓF	SHEETS	

	, <u></u>				
				-	
		* Various			
	F.A. RTE.	** (106BR. SECTION	)M. (4B-2)M & 17	77-4B-3)M DTAL SHEET EETS NO.	
TO STA.	•	•• ILLINOI	Various s CONTRACT N	26 3	
	FED. ROAD DIS		NU TRUJELI		

STA.