

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(111CS) W&RS-21	GRUNDY	85	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

HSIP  
URBAN  
90% FED  
10% STATE  
F

HSIP  
90% FED  
10% STATE  
URBAN

FAP 326 (IL ROUTE 47)				CONSTRUCTION TYPE CODE	
SUMMARY OF QUANTITIES				RWY	TS
CODE NO.	ITEM	UNIT	TOTAL	I000-2A	y031-1F
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.7	0.3
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	0.7	0.3
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.85	0.15
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	202	202	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	48	48	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3702	3702	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1234	1234	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	32	32	
* 72000200	SIGN PANEL - TYPE 2	SQ FT	85	85	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	405.6	405.6	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4149.2	4149.2	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4310.6	4310.6	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	826.3	826.3	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	657.2	657.2	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	458.4	458.4	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	191	191	
* 78200300	PRISMATIC CURB REFLECTOR	EACH	16	16	

FAP 326 (IL ROUTE 47)				CONSTRUCTION TYPE CODE	
SUMMARY OF QUANTITIES				RWY	TS
CODE NO.	ITEM	UNIT	TOTAL	I000-2A	y031-1F
78300100	PAVEMENT MARKING REMOVAL	SQ FT	730	730	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	165	165	
* 80500200	SERVICE INSTALLATION, TYPE B	EACH	3		3
* 81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	406		406
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	3342		3342
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	171		171
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	42		42
* 81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	1470		1470
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	606		606
* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	515		515
* 81300948	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 24" X 24" X 10"	EACH	8		8
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	20		20
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2		2
* 81700120	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 6	FOOT	350		350
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	2400		2400
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3997		3997
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4		4
* 82500505	LIGHTING CONTROLLER, SPECIAL	EACH	3		3

27 MAR 08

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
IL ROUTE 47  
GRUNDY COUNTY

SCALE: NONE  
DATE: 09/2007  
DRAWN BY: KHH  
CHECKED BY: FML