

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(111CS) W&RS-21	RUNDY	85	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

60405740, 60500040, 60500060 MANHOLE, INLET, FRAME AND GRATE REMOVAL				
LOCATION	FRAMES AND GRATES	MANHOLES	INLETS	
STATION	OFFSET	60405740	60500040	60500060
1239	LEFT		1	
1241	LEFT	1		1
1241	RIGHT	1		1
1241	RIGHT		1	
1457	LEFT	1		1
1476	LEFT		1	
1488	LEFT	1		1
1488	RIGHT	1		1
1621	LEFT		1	
1630	LEFT	1		1
1630	RIGHT	1		1
1751	LEFT	1		1
1798	LEFT	1		1
1804	RIGHT	1		1
1819	LEFT		1	
1897	LEFT		1	
1900	LEFT	1		1
1900	RIGHT	1		1
2044	LEFT		1	
2078	LEFT	1		1
2118	LEFT	1		1
2190	LEFT		1	
2245	LEFT	1		1
2291	RIGHT	1		1
2299	RIGHT	1		1
2300	LEFT	1		1
2626	LEFT	1		1
2627	RIGHT	1		1
2633	LEFT	1		1
2635	RIGHT	1		1
2797	RIGHT	1		1
2807	RIGHT		1	
2889	RIGHT		1	
2890	LEFT	1		1
2890	RIGHT	1		1
2950	RIGHT		1	
TOTAL		25	11	25

60608600 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06			
LOCATION	OFFSET	QUANTITY	
ENTRANCE		FOOT	
16+04.99	LT	22.5	
22+59.94	RT	10.2	
22+59.08	LT	18.7	
WEST BENTON ISLAND	LT	30.9	
EAST BENTON ISLAND	RT	24.1	
TOTAL		106.4	

78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"			
LOCATION	APPLICATION	QUANTITY	
STATION TO STATION		FOOT	
10+56.3	13+97.5	SKIP DASH	300.0
14+77.5	17+32.5	SKIP DASH	280.0
18+15.5	20+54.5	SKIP DASH	160.0
21+45.0	23+84.5	SKIP DASH	160.0
24+71.0	27+25.5	SKIP DASH	160.0
27+95.0	31+10.0	SKIP DASH	140.0
MAIN	CROSSWALK	529.4	
JEFFERSON	CROSSWALK	496.0	
JACKSON	CROSSWALK	495.3	
NORTH	CROSSWALK	518.7	
CHAPIN	CROSSWALK	510.6	
BENTON	CROSSWALK	560.4	
TOTAL		4310.6	

78100100 RAISED REFLECTIVE PAVEMENT MARKER		
LOCATION	QUANTITY	
STATION TO STATION	EACH	
11+38.4	13+97.5	28
14+77.5	17+32.5	28
18+15.5	20+54.5	30
21+45.0	23+84.5	30
24+71.0	27+25.5	30
27+95.0	31+10.0	35
NORTH		3
BENTON		7
TOTAL		191

60625800 ISLAND PAVEMENT (SPECIAL)			
LOCATION	OFFSET	QUANTITY	
ISLAND		SO. YD.	
WEST BENTON ISLAND	LT	18.3	
EAST BENTON ISLAND	RT	22.2	
TOTAL		40.5	

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"			
LOCATION	QUANTITY		
STATION TO STATION	FOOT		
10+56.3	10+65.0	8.7	
18+94.5	20+54.5	116.0	
21+45.0	23+05.0	116.0	
25+55.5	27+25.5	126.0	
27+95.0	30+16.67	143.0	
MAIN INTERSECTION		18.5	
NORTH INTERSECTION		62.0	
BENTON INTERSECTION		64.0	
EAST BENTON ISLAND		86.2	
WEST BENTON ISLAND		85.9	
TOTAL		826.3	

78200300 PRISMATIC CURB REFLECTOR		
LOCATION	QUANTITY	
	EACH	
WEST BENTON ISLAND		8
EAST BENTON ISLAND		8
TOTAL		16

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS				
LOCATION	NO. OF	QUANTITY		
STATION TO STATION	ARROWS	SO. FT.		
11+38.4	13+97.5	4	62.4	
14+77.5	17+32.5	4	62.4	
18+15.5	20+54.5	5	78.0	
21+45.0	23+84.5	5	78.0	
24+71.0	27+25.5	5	78.0	
27+95.0	31+10.0	3	46.8	
TOTAL			405.6	

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		
LOCATION	QUANTITY	
STATION TO STATION	EACH	
11+38.4	31+10.0	165
TOTAL		165

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24				
LOCATION	OFFSET	QUANTITY		
STATION TO STATION		FOOT		
11+88.7	14+16.7	LT	248.8	
11+86.5	14+19.3	RT	246.2	
14+58.9	17+52.5	LT	329.5	
14+58.0	17+57.7	RT	325.0	
17+93.1	20+77.7	LT	330.1	
17+92.9	20+85.0	RT	342.9	
21+18.5	24+04.1	LT	335.0	
21+14.7	24+08.6	RT	350.5	
24+50.8	27+43.1	LT	335.8	
24+47.2	27+47.6	RT	385.3	
27+98.5	31+10.0	LT	332.0	
27+97.9	31+10.0	RT	347.6	
WEST BENTON ISLAND	LT		30.9	
EAST BENTON ISLAND	RT		35.0	
TOTAL			3974.6	

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"			
LOCATION	QUANTITY		
STATION TO STATION	FOOT		
10+56.3	10+65.0	17.3	
11+41.5	13+97.5	512.0	
14+77.5	17+32.5	510.0	
18+15.5	20+54.5	478.0	
21+45.0	23+84.5	479.0	
24+71.0	27+15.5	489.0	
28+04.5	31+10.0	1017.3	
MAIN ST. INTERSECT.		24.2	
NORTH ST. MEDIAN		406.6	
BENTON		215.8	
TOTAL		4149.2	

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"		
LOCATION	QUANTITY	
	FOOT	
MAIN MEDIAN		16.2
NORTH MEDIAN		3.8
BENTON WEST ISLAND		20.7
BENTON EAST ISLAND		21.4
IL 47 MEDIAN		52.1
CROSSWALK TRAVERSING		543
TOTAL		657.2

XX005565 REMOVE AND RESET BRICK PAVERS		
LOCATION	QUANTITY	
	SO. FT.	
NE QUAD NORTH ST.		211.0
SW QUAD CHAPIN ST.		34.2
NW QUAD CHAPIN ST.		31.5
SW QUAD BENTON ST.		13.2
TOTAL		289.9

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"		
LOCATION	QUANTITY	
INTERSECTION	FOOT	
JEFFERSON		26.3
JACKSON		72.8
NORTH		123.1
CHAPIN		77.0
BENTON		159.2
TOTAL		458.4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 IL ROUTE 47  
 GRUNDY COUNTY

SCALE: NONE  
 DATE: 09/2007

DRAWN BY: KHH  
 CHECKED BY: FML