

|       |     |          |        |       |     |
|-------|-----|----------|--------|-------|-----|
| ROUTE |     | SECTION  | COUNTY | SHEET |     |
| MKD.  | FAP | 103 RS-3 | PEORIA | TOTAL | NO. |
| IL 90 | 661 |          |        | 21    | 10  |

D-94-068-02  
CONTRACT # 68259

| EPOXY PAVEMENT MARKINGS        |                |                 |                |                 |                 |                               |
|--------------------------------|----------------|-----------------|----------------|-----------------|-----------------|-------------------------------|
| LOCATION                       | 4" WHITE (FT.) | 4" YELLOW (FT.) | 8" WHITE (FT.) | 12" WHITE (FT.) | 24" WHITE (FT.) | LETTERS AND SYMBOLS (SQ. FT.) |
| STA. 5+00 TO STA. 31+88 (BK)   | 5377           | 670             | -              | -               | -               | -                             |
| STA. 32+00 (AH) TO STA. 53+77  | 4354           | 545             | -              | -               | -               | -                             |
| BRIDGE OMISSION                | -              | -               | -              | -               | -               | -                             |
| STA. 53+77 TO STA. 54+42       | 132            | 17              | -              | -               | -               | -                             |
| STA. 54+40 TO STA. 58+36       | 792            | 98              | -              | -               | -               | -                             |
| STA. 58+36 TO STA. 65+60.1     | 1448           | 905             | -              | -               | 39              | 61.2                          |
| RAILROAD OMISSION              | -              | -               | -              | -               | -               | -                             |
| STA. 65+60.1 TO STA. 65+69.1   | -              | -               | -              | -               | -               | -                             |
| STA. 65+69.1 TO STA. 72+07     | 1276           | 798             | -              | -               | 39              | 61.2                          |
| STA. 72+07 TO STA. 131+93 (BK) | 11972          | 3157            | -              | -               | -               | -                             |
| STA. 132+00 (AH) TO 137+71     | 1142           | 143             | 337            | 137             | 29              | -                             |
| SIDEROAD- HAKES ROAD           | -              | -               | -              | -               | -               | -                             |
| STA. 10+29.9 TO STA. 11+00     | 141            | 141             | -              | -               | -               | -                             |
| SUBTOTAL                       | 26634          | 6474            | 337            | 137             | 107             | 122.4                         |
| TOTAL                          | 33108          |                 | 337            | 137             | 107             | 122.4                         |

NO PASSING ZONES:

RT. STA. 57+84 TO RT. STA. 65+60  
LT. STA. 65+69 TO LT. STA. 72+16  
RT. STA. 77+36 TO RT. STA. 84+15  
LT. STA. 85+38 TO LT. STA. 94+23

\*AREA OF RT. TURN ARROW= 15.6 SQ. FT.  
AREA OF "R"= 3.6 SQ. FT.  
AREA OF "X"= 54.0 SQ. FT.

| RAISED REFLECTIVE PAVEMENT MARKER REMOVAL |      |
|---|------|
| LOCATION                                  | EACH |
| STA. 5+00 TO STA. 137+64                  | 168  |
| TOTAL                                     | 168  |

| CONSTRUCT TEST STRIP |      |
|----------------------|------|
| LOCATION             | EACH |
| JOBSITE              | 1    |
| TOTAL                | 1    |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**