## GENERAL NOTES:

STANDARDS 1.NO EXCAVATION ANTICIPATED ON THIS PROJECT WHICH WOULD AFFECT UTILITIES. SHOULD ANY EXCAVATION DEVIATING FROM THAT 701001-01 ANTICIPATED BE REQUIRED, J. U. L. I. E. WILL BE NOTIFIED A MINIMUM OF 701006-02 48 HOURS IN ADVANCE - (800) 892-0123. 701011-01 701101-01 2. THE FOLLOWING APPLICATION RATES WERE USED FOR QUANTITY CALCULATIONS: 701106-01 701301-02 LEVELING BINDER 0.056 T / SY\*IN 701311-02 BIT. CONC. SURF. CSE. 0.056 T / SY\*IN 701426-02 .00038 T / SY PRIME COAT (BIT) 701501-04 PRIME COAT (AGG) .002 T / SY 701601-05 701701-05 3. THE THICKNESS OF BITUMINOUS MIXTURES SHOWN ON THE PLANS IS THE NOMINAL 780001-01 THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN 781001-02 SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE 000001-05 ON WHICH THE BITUMINOUS MIXTURE IS PLACED. 001006

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE TO THIS PROJECT:

HMA Surface HMA MIXTURE USES: US 136 US 136 SBS PG 70-22 PG 58-22 AC/PG: 4.0% @ N Design = 70 2.0% @ N Design = 30 DESIGN AIR VOIDS: BAM MIXTURE COMPOSITION: IL 9.5 OR IL 12.5 (GRADATION MIXTURE) Mix \*D\* N/A FRICTION AGGREGATE:

- 4. ALL ELEVATIONS SHOWN IN THE PLANS ARE U.S.G.S. MEAN SEA LEVEL DATUM.
- 5. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
- 6. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE TRAFFIC CONTROL DEVICES AT ALL TIMES DURING CONSTRUCTION ACTIVITIES AND SHALL COORDINATE THE ITEMS OF WORK IN ORDER TO KEEP HAZARD TRAFFIC INCONVIENCES TO A MINIMUM
- 7.ALL PAVEMENT MARKINGS SHALL BE VERIFIED BY RESIDENT/FIELD ENGINEER PRIOR TO THEIR PLACEMENT.

DISTRICT SIX	
EXAMINED July 8	20 08.
Some I House	
OPERATIONS ENGINEER	
EXAMINED Suly 8	20 <u>08</u>
PROGRAM IMPLEMENTATION ENGINE	ER
EXAMINED 8	20 <u>68</u>
PROGRAM DEVELOPMENT ENGINEER	

FILE NAME =	USER NAME '= medoniavj	DESIGNED -	REVISED -
c:\projects\d603408\shtgennotes.dgn		DRAWN - BMD	REVISED -
ŀ	PLOT SCALE = 100.0000 '/ IN.	CHECKED -	REVISED -
,	PLOT DATE = Jul-08-2008 01:21:56PM	DATE - 7/2/2008	REVISED -

STATE	: 01	FILLINOIS
DEPARTMENT	OF	TRANSPORTATION

SCALE:

GENERAL NOTES			F.A.P RTE.	SECTION	COUNTY	TOTAL	SHEET NO.		
					315	23RS-2	HANCOCK	15	2
							CONTRAC		72C31
SHEET NO	. OF	SHEETS	STA.	TO STA.	FED. RC	DAD DIST. NO.   ILLINOIS FED. A	IO PROJECT		