
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

EXISTING DECK BEAM

ROUTE NO.	SECTION	COUNTY		TOTAL SHEETS	SHEET NO.	SHEET NO.	
F.A.S. 1832	5BR-2	WASHINGTON		97	29	18	SHEETS
FED. ROAD OLST. NO. 7		BLLINDIS	FED. AID PROJECT-				

3

Contract #76949



NOTES

Detail I - With Bar Splicer or Couplers: Connect one (1) 1"x7"x10" steel P to the top layer of couplers with 2-58" \$\phi\$ bolts screwed to coupler at approximate & of each barrier panel.

Detail II - With Extended Reinforcement Bars: Connect one (1) 1"x7"x10" steel P to the concrete slab or concrete wearing surface with 2-58'0 Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate & of each barrier panel.

Cost of anchorage is included with Temporary Concrete Barrier. The I" x 7" x 10" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready to be placed.


SECTIONS THRU SLAB OR DECK BEAM

EXISTING SLAB

***Dimension shown is minimum required embedment into concrete. If hot-mix asphalt wearing surface is present, minimum embedment

shall be in addition to wearing surface depth.


*****If existing deck beam is to remain in place after stage construction, embedment shall only be into wearing surface and not into existing deck beam concrete.




NEW SLAB

DETAIL I

when "A" is greater than 3'-6".



**Wood blocks may be omitted when required to provide minimum stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.



STEEL RETAINER & 1" x 7" x 10"

* Required only with Detail II

TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION F.A.S. RTE. 1832 - SEC. 5BR-2 WASHINGTON COUNTY STATION 1453+11.50 STRUCTURE NO. 095-0077

DESIGNED Phillip R. Litchfiel CHECKED Nicholas R. Barne DRAWN Gregory D. Farmer CHECKED PRL/NRB R-27 9-3-07

.\projects\farmergd\0950077.dgn = 1/28/2008 ii: 07:32 AM