

PAVEMENT MARKING SCHEDULE

STATION	STATION	DESCRIPTION	SHORT-TERM PAVT MKING	TEMP PVT MK LN 4"	TEMP PVT MK LN 8"	TEMP PVT MK LN 12"	TEMP PVT MK LN 24"	TEMP PAVT MK L&S L&S	WORK ZONE PAVT MK REM	THPL PVT MK LTR & SYM	THPL PVT MK LN 4"	THPL PVT MK LN 8"	THPL PVT MK LN 12"	THPL PVT MK LN 24	RAISED REFL PAVT MKR (NOTE 2) (EACH)	PRISMATIC CURB REFL (EACH)	PT PVT MK- RAISED MED (SQ FT)	PAINT PVT MARK CURB (FOOT)
(FOOT)			(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(SQ FT)	(FOOT)
RAMP 4																		
LT 0+40	LT 0+46	Med Ramp Nose															27	
LT 0+46	LT 0+78	CC&G																35
LT 0+40	LT 1+78	LT EOP		144					48		144							
RT 0+49	RT 1+78	RT EOP		162					53		162							
RT 0+51	RT 0+63	Stop Bar					18		36					18				
FAU RTE. 9111 (HORSESHOE LAKE ROAD)																		
LT 225+48	LT 225+81	Island			114	62			138			114	62					
LT 225+32	LT 225+38	Med Ramp Nose															28	
LT 225+38	LT 225+86	EB Med Curb													3		49	
LT 225+38	LT 231+67	WB CC&G		629					208		629				17			
LT 230+95	LT 231+67	WB Med Curb															48	
LT 231+67	LT 231+73	Med Ramp Nose															24	
LT 226+12	LT 231+72	WB EOP		560					185		560							
LT 225+82	LT 231+72	WB Ln Line	118	589					194		589				16			
LT 225+57	LT 225+57	WB Stop Bar					14		28					14				
LT 226+55	LT 226+63	WB Arrows						15.6	16	15.6								
LT 228+85	LT 228+93	WB Arrow						15.6	16	15.6								
LT 225+38	LT 231+67	EB CC&G		629					208		629					32		
LT 225+86	LT 228+26	EB Lt. Turn Ln		62					20		62							
LT 228+26	LT 232+11	EB Lt. Turn Ln	77	385					127		385				11			
LT 228+97	LT 229+05	EB Arrow						15.6	16	15.6								
LT 231+12	LT 231+20	EB Arrow						15.6	16	15.6								
LT 231+15	LT 231+23	WB Arrow						15.6	16	15.6								
RT 231+67	RT 231+67	EB Stop Bar					12		24					12				
RT 225+07	RT 231+73	EB EOP		666					220		666							
RT 225+86	RT 228+25	EB Rt. Turn Ln		62					20		62							
RT 228+25	RT 231+98	EB Rt. Turn Ln	75	373					123		373			10				
RT 232+11	LT 232+11	EB Stop Bar					14		28					14				
RT 228+97	RT 229+05	EB Arrow						15.6	16	15.6								
RT 231+12	RT 231+20	EB Arrows						15.6	16	15.6								
RT 232+03	RT 232+28	Island			90	28			88			90	28					
FOURNIE LANE																		
LT 10+54	LT 10+73	LT EOP		52					17		52							
LT 10+65	LT 10+72	Stop Bar					24		48					24				
RT 10+22	RT 10+73	RT EOP		99					33		99							
EASTPORT PLAZA DRIVE																		
RT 47+84	RT 48+64	RT EOP		106					35		106							
RT 47+89	RT 48+02	Stop Bar					18		36					18				
RT 48+16	RT 48+65	Dbl Ln Line	5	48					16		48				3			
RT 48+50	LT 48+58	Lt Turn Arrow						15.6	16	15.6								
RT 48+64	LT 48+81	Bike Path				243			243				*	243				
LT 47+93	LT 47+93	Stop Bar					12		24					12				
LT 47+93	LT 48+66	Lane Line	15	73					24		73							
LT 47+92	LT 48+67	LT EOP		166					55		166							
LT 47+93	LT 48+07	Stop Bar					18		36					18				
LT 48+18	LT 48+18	Stop Bar					12		24					12				
RT 48+78	RT 49+04	RT EOP		26					9		26							
RT 48+79	RT 49+04	Dbl Ln Line	3	25					8		25			3				
LT 48+80	LT 49+04	Lane Line	5	24					8		24							
LT 48+81	LT 49+04	LT EOP		24					8		24							
FAU RTE. 9111 (HORSESHOE LAKE ROAD)																		
RT 232+64	RT 232+91	Island			88	34			93			88	34					
RT 233+84	RT 242+85	RT EOP		901					297		901							
LT 232+95	LT 242+85	Median	396	3960		255			1562		3960		255		52			
LT 233+04	LT 233+04	Stop Bar					12		24					12				
LT 232+71	LT 232+78	WB Stop Bar					23		46					23				
LT 232+71	LT 235+45	WB Ln Line	55	274					90		274				8			
LT 233+50	LT 233+58	WB Arrows						15.6	16	15.6								
LT 234+90	LT 234+98	WB Arrow						15.6	16	15.6								
LT 235+45	LT 237+25	WB Ln Line		47					16		47							
LT 233+14	LT 242+85	LT EOP		971					320		971							
TOTAL			749	11057	292	622	177	156	4980	156	11057	292	622	177	103	52	79	132

PAVEMENT MARKING NOTES:

1. RAISED REFLECTIVE PAVEMENT MARKER QUANTITY INCLUDES THE FOLLOWING TYPES:

64 EACH EACH
45 EACH EACH
EACH EACH
109 EACH EACH

ONE-WAY AMBER MARKERS
ONE-WAY CRYSTAL MARKERS
TWO-WAY AMBER MARKERS
TOTAL

* TO BE PAID FOR AS
PAINT PAVEMENT MARKING - LINE 12"
(7800/150)

EROSION CONTROL SCHEDULE

STATION	STATION	EROSION CONTROL BLANKET (SQ YD)	TEMP EROS CONTR SEED (POUND)	TEMPORARY DITCH CHECKS (EACH)	PERIMETER EROS BAR (FOOT)	INLET & PIPE PROTECTION (EACH)
RAMP 4						
RT 1+56						1
LT 0+73	LT 1+78				105	
HORSESHOE LAKE ROAD						
LT 226+40						1
LT 226+50				1		
RT 226+50						
LT 226+65						1
LT 226+90						1
LT 227+15						1
LT 227+40						1
LT 227+65						1
LT 227+90						1
LT 228+15						1
LT 228+40						1
LT 228+65						1
LT 228+90						1
LT 229+15						1
LT 229+40						1
LT 229+65						1
LT 229+90						1
LT 230+00						1
LT 230+80						1
LT 231+50				1		
LT 232+92						1
RT 233+02						1
LT 233+50				1		
RT 238+00				1		
RT 239+66						1
LT 239+66						1
RT 1+78 (RAMP 4)	LT 232+17				741	
LT 225+06.5	LT 232+45					
RT 225+06.5	RT 232+29	1598	60			
RT 225+06.5	RT 232+80		20			
RT 225+38	RT 231+87				657	
LT 232+45	LT 242+85		20			
LT 232+71	LT 242+90				1031	
RT 232+80	RT 242+85		20			
RT 233+01	RT 242+90				993	
EASTPORT PLAZA DRIVE						
RT 48+03	RT 48+63				64	
LT 48+09	LT 48+67				65	
RT 48+81	RT 49+09				28	
LT 48+85	LT 49+07				22	
TOTALS		1598	120	5	3706	22

PIPE UNDERDRAIN SCHEDULE

STATION	STATION	CONC HDWL FOR P DRAIN (EACH)	PIPE UNDERDRAINS 4 (FOOT)	PIPE UNDERDRAINS 4 SP (FOOT)
FAU RTE. 9111 (HORSESHOE LAKE ROAD)				
LT 226+14	LT 228+90	1	276	20
LT 228+90	LT 231+70	1	280	20
LT 233+20	LT 236+57	1	336	11
LT 236+60	LT 239+60	1	300	9
LT 239+72	LT 242+85	1	313	9
RT 225+06.5	RT 228+38	1	333	10
RT 228+42	RT 231+64	1	322	14
RT 233+32	RT 236+60	1	333	23
RT 236+64	RT 239+60	1	296	4
RT 239+72	RT 242+85	1	313	4
Ramp 4				
LT 0+92	LT 1+54		62	
LT 1+54	LT 1+78	1	23	10
RT 1+60	RT 1+78	1	18	10
TOTAL		12	3205	144

NOTES: 1. SEE STD 601001 FOR MORE INFORMATION.

Rev. Sheet 7-17-08