

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL	ACHSTP	ACM	ACHSTP	ACHSTP				
				1000-1A	1000-1A	Y031-1F	Y031-1F				
			QUANTITIES	ROADWAY	ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNALS				
					RT TURN LANE	I-255	PLAZA DR.				
				HSIP	STP	RAMPS 3 & 4	FOURNIE LN.				
				90% FEDERAL 10% STATE	80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	5% Collinsville 90% FEDERAL 5% STATE				
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	56			56					
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	10			2	8				
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1				1				
81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1222			703	519				
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	250				250				
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1480				1480				
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1710			768	942				
81900205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	FOOT	24			4	20				
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	2				2				
83027500	LIGHT POLE, ALUMINUM, TRANSFORMER BASE, 50 FT. M.H., TENON MOUNT - TWIN	EACH	1				1				
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	21			14	7				
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	1				1				
84200700	LIGHTING FOUNDATION REMOVAL	EACH	3			2	1				
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2			2					
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1				1				
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1				1				
87100105	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 4F	FOOT	506			272	234				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1211				1211				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1257				1257				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1991			458	1533				
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1				1				
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1				1				
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1				1				
87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1				1				
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3				3				
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	64				64				

* SPECIALTY ITEMS