

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

URBAN TOTAL	ACHETP	ACM	ACHETP	ACHETP				
	1000-1A	1000-1A	Y031-1F	Y031-1F				
	ROADWAY	ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNALS				
		RT TURN LANE	I-255	EASTPORT				
	HSIP	STP	RAMPS 3 & 4	PLAZA DR.				
				FOURNIE LN.				
	90% FEDERAL 10% STATE	80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	51 Collinsville 90% FEDERAL 10% STATE				

CODE NO	ITEM	UNIT	QUANTITIES	90% FEDERAL 10% STATE	80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE				
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4				4				
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4				4				
88040110	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2				2				
88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2				2				
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2				2				
* 88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2				2				
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	8				8				
88500100	INDUCTIVE LOOP DETECTOR	EACH	15			1	14				
88600100	DETECTOR LOOP, TYPE I	FOOT	2280			427	1853				
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1			1					
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	60			60					
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	660			660					
89502380	REMOVE EXISTING HANDHOLE	EACH	1			1					
X0323221	PLUG AND ABANDON EXISTING PIPE	CU YD	4	4							
* X7800100	PAINT PAVEMENT MARKING - RAISED MEDIAN	SQ FT	79	79							
X7800200	PAINT PAVEMENT MARKING CURB	FOOT	132	132							
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5						
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	2771	2271	500						
Z0050900	REMOVE CONCRETE FOUNDATION	EACH	8	6	2						
© Z0076600	TRAINEES	HOURL	500	500							

© Y080
 * SPECIALTY ITEMS