

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	22	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

- * FAS 1909 & FAP 322
- ** DS PAVEMENT PRESERVATION FY08
- *** JACKSON AND UNION COUNTIES

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FAP 322 (US 51) IL 146 TO BODY BARN RD.	FAP 322 (US 51) BODY BARN RD. TO I-57 CONNECTOR	FAS 1909 (IL 127) TOMCAT LN. TO UNION/JACKSON CO. LINE
				LOC. 1 RURAL	LOC. 2 RURAL	LOC. 3 RURAL
				100% STATE	100% STATE	100% STATE
				MICROSURFACING UNION	MICROSURFACING UNION	MICROSURFACING JACKSON
				1000	1000	1000
				QUANTITY	QUANTITY	QUANTITY
X0325223	FIBER ASPHALT	POUND	69,330	33386	19613	16331
X4480205	MICRO-SURFACING, 2 PASSES, TYPE 2	SQ YD	198,426	84126	50792	63508
Z0040315	PILOT CAR	DAY	8	2	2	4
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	17,858.2	7571.3	4571.2	5715.7
67100100	MOBILIZATION	L SUM	1	0.3	0.3	0.4
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.3	0.3	0.4
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19,300	7841	4600	6859
70300210	TEMPORARY PAVEMENT MARKING, LETTERS ^{AND} SYMBOLS	SQ FT	254.8	182.0	72.8	
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	210,451	79383	41841	89227
70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	1,133	694	439	
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	66	66		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	75,818	28784	15326	31708
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS ^{AND} SYMBOLS	SQ FT	254.8	182.0	72.8	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	210,451	79383	41841	89227
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	1,133	694	439	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	66	66		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,012	493	229	290
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,012	493	229	290

* SPECIALTY ITEMS