## ENTRANCE DETAIL SCALE : 1" = 5' SCHEDULE OF ENTRANCES VAR. - SEE SCHEDULE STATION WIDTH SQ YDS REQUIRED 16+75 22+10 24+40 43+60 43+70 55+60 55+85 22' 22' 22' 22' 22' 22' 15.0 15.0 15.0 15.0 15.0 15.0 105.0 SQ YD \*CONSISTS OF 5" BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX "C" N50 -- CENTERLINE PROR SURF. INTERSECTIONAL DETAIL STA. 3+35 Total Area LT. 159.7 SQ YDS Total Area RT. 159.7 SQ YDS Thickness Required 5" COMP Incidental Hot-Mix Asphalt Surfacing Required LT. Incidental Hot-Mix Asphalt Surfacing Required RT. 44.7 TON 44.7 TON Hot-Mix Asphalt Surface Removal Butt Joint LT. & RT. 122.2 SQ YDS \*CONSISTS OF 5" BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX "C" N50 300,745, 110 ENDING INTERSECTION DETAIL STA. 57+00 Total Area LT. 126.0 SQ YDS Total Area RT.

Thickness Required


\*CONSISTS OF 5" BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX "C" N50

Incidental Hot-Mix Asphalt Surfacing Required LT.
Incidental Hot-Mix Asphalt Surfacing Required RT.



## TYPICAL CROSS SECTION

THE THICKNESS OF BITUMINOUS MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS DEVIATION FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.



## MAILBOX TURNOUT DETAIL

SCALE: 1"=10"


EDGE PROP. SURF.

CENTERLINE PROP. SURF.

MAILBOX TURNOUTS

STATION SQ YDS REQUIRED SQ YD

\*CONSISTS OF 5" BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX "C" N50



NOTE: REFER TO STANDARD 701901 FOR ERECTION OF SIGNS AND PLACEMENT OF TYPE III BARRRICADES. TY. A LOW INTENSITY LIGHTS ARE REQUIRED ABOVE THE FIRST TWO WARNING SIGNS FROM EACH DIRECTION AS PER STANDARD BLR 22-5

127.0 SQ YDS

5" COMPL.

166.6 SQ YDS

35.3 TON 35.6 TON