	<del></del>	
SE003 `	B4	_
	REVISION	
	DATE	

## SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	as Awarded Quantities	AS BUILT QUANTITIES
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152480	SHOULDER ADJUSMENT	S.Y.	885	
AR156513	SEPARATION FABRIC	S.Y.	2,869	
AR156520	INLET PROTECTION	EACH	5	
AR156531	EROSION CONTROL BLANKET	S.Y.	1,415	
AR201610	BITUMINOUS BASE COURSE	TON	350	
AR201660	BITUMINOUS CRACK REPAIR	L.F.	650	
AR201910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	46	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	1,350	
AR401610	BITUMINOUS SURFACE COURSE	TON	1,000	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	5,381	
AR401665	BITUMINOUS PAVEMENT SAWING	L.F.	317	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	2,869	
AR602510	BITUMINOUS PRIME COAT	GAL.	1,005	
AR603510	BITUMINOUS TACK COAT	GAL.	1,238	
AR701212	12" CMP	L.F.	105	
AR751051	SLOTTED DRAIN	L.F.	100	
AR751410	INLET	EACH	1	

I	N	D	EX	TO	SH	EE.	TS

SHEET NO.	DESCRIPTION	
1	COVER SHEET	******************
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS	
3	PROPOSED SAFETY PLAN	
4	EXISTING SITE PLAN	
5	PROPOSED PAVEMENT PREPARATION PLAN	
6	EXISTING AND PROPOSED TYPICAL SECTIONS	
7	PROPOSED CONSTRUCTION PLAN	
8	PROPOSED STORMWATER POLLUTION PREVENTION PLAN	
9	PROPOSED PLAN AND PROFILE NORTH ALIGNMENT	
10	PROPOSED PLAN AND PROFILE — CENTER ALIGNMENT	
11	PROPOSED PLAN AND PROFILE - SOUTH ALIGNMENT	
12	PROPOSED CROSS SECTIONS - NORTH ALIGNMENT	
13	PROPOSED CROSS SECTIONS - CENTER ALIGNMENT	
14	PROPOSED CROSS SECTIONS - SOUTH ALIGNMENT	

SHELBY COUNTY AIRPORT SHELBYVILLE, IL

O-Copyright Henson Professional Services Inc. 2008
Hanson Professional Services Inc. 4255 South Study Street Springfact Illinos 827092886
Offices Nationalide

REHABILITATE
T-HANGAR PAVEMENTS
SUMMARY OF QUANTITIES
AND
INDEX TO SHEETS

2 of 14 sheets