



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 23, 2025

SUBJECT: FAP Route 301 (US 20) & FAP Route 654/FAS Route 1087 (IL 73)
Section (22,107)A
Stephenson County
Contract No. 64U79
Item No. 25, August 1, 2025 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Table of Contents to the Special Provisions.
2. Added page 65 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
COMPLETION DATE PLUS WORKING DAYS	1
TRAFFIC CONTROL PLAN	2
CONSTRUCTION LAYOUT SPECIAL UTILIZING GPS EQUIPMENT	3
FENCE REMOVAL	4
PIPE CULVERTS (TEMPORARY)	4
TOPSOIL EXCAVATION AND PLACEMENT (SPECIAL)	4
FURNISHED EXCAVATION (SPECIAL)	5
SEEDING, CLASS 7 (SPECIAL)	6
WETLAND AREAS	6
AVAILABILITY OF ELECTRONIC FILES	7
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	7
STATUS OF UTILITIES	8
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)	10
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES; CONCRETE, AND MORTAR (BDE)	11
COMPENSABLE DELAY COSTS (BDE)	21
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	24
EROSION CONTROL BLANKET (BDE)	27
FUEL COST ADJUSTMENT (BDE)	29
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE)	32
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	32
SEEDING (BDE)	33
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	38
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	39
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	39
SUBMISSION OF PAYROLL RECORDS (BDE)	39
SURVEYING SERVICES (BDE)	40
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	41
WEEKLY DBE TRUCKING REPORTS (BDE)	41
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	41
SWPPP	44
STABILIZED CONSTRUCTION ENTRANCE	65

Revised July 16, 2025
Revised July 23, 2025

STABILIZED CONSTRUCTION ENTRANCE

Description. This work consists of constructing, maintaining and removing a stabilized pad of course aggregate underlain with geotechnical fabric at the locations where construction traffic will be entering and leaving the work zone. The final locations of the stabilized pad are subject to the approval of the Engineer. This work shall be performed in accordance with the applicable portions of Sections 202, 210, 1004 and 1080 of the Standard Specifications, the details in the plans, SWPPP, or as directed by the Engineer.

Materials. Aggregate shall consist of course aggregate gradations CA-1, CA-2, CA-3, or CA-4 meeting the requirements of Article 1004.04. Aggregate thickness shall be as detailed on the plans.

Geotechnical fabric shall meet the requirements of Article 1080.02.

General. Excess or unsuitable excavated materials shall be disposed of in accordance with Article 202.03.

The aggregate surface coarse shall be compacted to the satisfaction of the Engineer.

The Contractor shall restore the stabilized construction entrance as needed for the duration of the contract.

The Contractor shall perform a final restoration of the entrances to the satisfaction of the Engineer just prior to end of the contract.

The stabilized construction entrances shall remain in place at the end of the contract, and not be removed.

Method of Measurement. The stabilized construction entrance will be measured in place and the area computed in square yards.

Basis of Payment. This work will be paid for at the contract unit price per square yard for STABILIZED CONSTRUCTION ENTRANCE, which price shall be payment in full for all excavation, except excavation in rock; removal and disposal of excavated materials; geotechnical fabric; furnishing, placing, and compacting coarse aggregate; maintenance and restoration as required, and for all labor, tools and equipment necessary to construct the work as specified.

Added July 23, 2025