



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 21, 2025

SUBJECT: Multi-Use Trail  
Section 23-00131-00-BT (City of Marion)  
Williamson County  
Contract No. 99760  
Item 069  
August 1, 2025 Letting  
Addendum (B)

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Schedule of Prices**
- 2. Revised Plan Sheets 2 & 4**
- 3. Revised page 3 of the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

## **TRAFFIC CONTROL ITEMS**

The traffic control shall be in accordance with the applicable sections of the Standard Specifications for Road and Bridge Construction, the guidelines contained in the Illinois Manual on Uniform Traffic Control Devices for Streets and Highways, the Supplemental Specifications, these special provisions and any special details and highway standards contained herein and in the plans. Special attention is called to Art. 107.09 and 107.14 of the Standard Specifications.

The applicable Traffic Control Standards for this project are:

- 701101-05 Off-Road Operations, Multilane, 15' to 24" from Pavement Edge
- 701301-04 Lane Closure, 2L 2W, Short Time Operations
- 701501-06 Urban Lane Closure, 2L, 2W, Undivided
- 701601-09 Urban Lane Closure, Multilane, 1W or 2W with non-traversable median
- 701801-06 Sidewalk, Corner or Crosswalk Closure
- 701901-10 Traffic Control Devices

The Contractor shall insure that all businesses and residences always have access to their properties during construction. Modifications to the Traffic Control Standards to fit field conditions shall be incidental to the pay items included below.

Any side road flaggers required at the request of the Engineer during while Standard 701501 is being utilized shall be included in the lump-sum cost for TRAFFIC CONTROL AND PROTECTION STANDARD 701501.

Payment for this work shall be at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION STANDARD 701501, TRAFFIC CONTROL AND PROTECTION STANDARD 701601 and TRAFFIC CONTROL AND PROTECTION STANDARD 701801.

## **MAINTAINING TRAFFIC SIGNS**

When it becomes necessary, because of construction to remove the traffic signs, the Contractor shall make provisions to maintain the traffic signs at a temporary location fully visible to the motorist. If it is not possible to make the temporary installation post mounted, the traffic sign