

P:\2320800-Marion\AR\destoCOTrail\01\_CADD\Marion\02 - IOS - NOTES - STANDARDS.dwg 6-12-25 07:48:55 AM mkkumrey

GENERAL NOTES



1. UNLESS MODIFIED BY THE PROJECT SPECIFICATIONS, ALL SITE WORK SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION," LATEST EDITION. HOWEVER, STORM SEWER, SANITARY SEWER AND WATER LINE WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS," LATEST EDITION. ALL SITE WORK SHALL COMPLY WITH THE ILLINOIS ACCESSIBILITY CODE.
2. THE LOCATIONS, SIZE, MATERIAL, DESCRIPTION OR TYPE OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL ARRANGE TO HAVE ALL UNDERGROUND UTILITIES LOCATED AND SUITABLY MARKED. THE UTILITIES ON THIS PROJECT SHALL BE CONTACTED BY THE CONTRACTOR BY CALLING THE JOINT UTILITY INFORMATION FOR EXCAVATORS (JULIE), PHONE 1-800-892-0123.
3. RADII DENOTED BY ASTERISKS(\*) ARE APPROXIMATE AND TO BE FIT IN THE FIELD BETWEEN THE NEW CURB AND EXISTING CURB.
4. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RESTORE THE GRADE TO THE DESIGN ELEVATIONS CHANGED BY NATURAL CAUSES UNTIL ACCEPTED BY THE OWNER FOR COMPLIANCE TO PLANS.
5. THE CONTRACTOR SHALL PERFORM IN THE BEST AND MOST WORKMANLIKE MANNER A COMPLETE GRADING AND COMPACTION OPERATION AS SHOWN ON THE PLANS, OR AS STATED IN THE SPECIFICATIONS PREPARED BY THE ENGINEER.
6. THE CONTRACTOR SHALL CONFINE HIS WORK WITHIN THE DESIGNATED WORK AREAS.
7. THE CONTRACTOR SHALL NOT DESTROY OR DAMAGE ANY TREES OTHER THAN THOSE WITHIN THE GRADING AREAS.

IDOT HIGHWAY STANDARDS

000001-08	Standard Symbols, Abbreviations and Patterns
001001-02	Areas of Reinforcement Bars
001006	Decimal of an Inch and of a Foot
280001-07	Temporary Erosion Control Systems
424001-12	Perpendicular Curb Ramps for Sidewalks
424006-06	Diagonal Curb Ramps for Sidewalks
424011-05	Corner Parallel Curb Ramps for Sidewalks
424016-06	Mid-Block Curb Ramps for Sidewalks
424021-07	Depressed Corner for Sidewalks
424026-04	Entrance Alley Pedestrian Crossings
542301-03	Precast Reinforced Concrete Flared End Section
542306-03	Precast Reinforced Concrete Elliptical Flared End Section
604001-05	Frame And Lids Type 1
606001-08	Concrete Curb Type B and Combination Concrete Curb and Gutter
701101-05	Off-Road Operations, Multilane, 15' to 24" from Pavement
701301-04	Lane Closure, 2L 2W, Short Time Operations
701501-06	Urban Lane Closure, 2L 2W, Undivided
701601-09	Urban Lane Closure, 1W 2W With Nontraversable Median
701901-10	Traffic control Devices
<del>BLR22-7</del>	<del>Typical App of Traffic Control Devices for Const on Rural Local Highways</del>
<del>BLR28-1</del>	<del>Concrete Curb Type B and Combination Curb and Gutter</del>
701801-06	Sidewalk, Corner or Crosswalk Closure
701901-10	Traffic Control Devices

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	23-00131-00-BT	WILLIAMSON	55	02
ILLINOIS		VA/HALFWAY RD. GREENWAY		
CONTRACT NO. 99760				

CONTRACT NO.: C-99-007-25



STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 184000435-0014				
REVISIONS		<div>© 2024 ALL RIGHTS RESERVED</div> <div><b>HORNER SHIFFRIN</b> 410 NORTH COURT ST. MARION, ILLINOIS 62959 PHONE: 618-993-6411 WWW.HORNERSHIFFRIN.COM</div> <div>GENERAL NOTES: HIGHWAY STANDARDS VA/HALFWAY ROAD GREENWAY CITY OF MARION, ILLINOIS</div>		
DATE	NO.			
7-17-25				
		Date FEB/2024	DR. By PLD	CK'D By JVZ
		Scale 1"=500'	Job No. 2320800	Sheet No. 2 of 55

P:\2320800-Marion\AR\destoC03Trai\01\_CADD\Marion\03-05 Summary of Quantities.dwg 6-12-25 07:57:09 AM mdkunrney

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	23-00131-00-BT	WILLIAMSON	55	04
ILLINOIS		VA/HALFWAY RD. GREENWAY		
CONTRACT NO. 99760				

SUMMARY OF QUANTITIES			LOCATION:	WEST MAIN ST./HALFWAY ROAD
			COUNTY:	WILLIAMSON
			FUNDING:	80% ITEP STATE / 20% STATE / 10% LOCAL
				BICYCLE/PEDESTRIAN TRAIL
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	0028
				URBAN
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1
50105220	PIPE CULVERT REMOVAL	FOOT	45	45
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1
54248510	CONCRETE COLLAR	CU YD	2.2	2.2
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	259	259
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	286	286
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	199	199
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	134	134
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	475	475
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	328	328
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	30	30
60260100	INLETS TO BE ADJUSTED	EACH	1	1
60600605	CONCRETE CURB, TYPE B	FOOT	194	194
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	270	270
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1348	1348
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
72000100	SIGN PANEL - TYPE 1	SQ FT	5	5
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	69	69
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	480	480
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	204	204

\* SPECIALTY ITEM

STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 184000435-0014			
REVISIONS		© 2024 ALL RIGHTS RESERVED	
DATE	NO.	 410 NORTH COURT ST, MARION, ILLINOIS 62959 618-993-6411 FAX 618-993-6750 WWW.HORNERSHIFFRIN.COM	
7-17-25			
		SUMMARY OF QUANTITIES - 2 VA/HALFWAY ROAD GREENWAY CITY OF MARION, ILLINOIS	
Date	FEB/2024	DR. By	PLD
		CK'D By	JVZ
Scale	N.T.S.	Job No.	2320800
		Sheet No.	4 of 55