

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	48	48					70300100	SHORT TERM PAVEMENT MARKING	FOOT	2438	2438					
40600300	AGGREGATE (PRIME COAT)	TON	213	213					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	55739	55739					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	121	121					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	700	700					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	18580	18580					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	247	247					*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	55739	55739					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	7438	7438					*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	121	121					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4761	4761					*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	389	389					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	1100	1100					78300100	PAVEMENT MARKING REMOVAL	SO FT	18620	18620					
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SO YD	294	294					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	377	377					
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SO YD	430	430					LR400510	REJUVENATING AGENT	GALLON	5430	5430					
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SO YD	354	354					X2020110	GRADING AND SHAPING SHOULDERS	UNIT	429	429					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	14,373	14,373					Z0010619	HOT IN-PLACE RECYCLING	SO YD	53127	53127					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3870	3870					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	257	257					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4														
67100100	MOBILIZATION	L SUM	1	1														
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1														

*©Z0076604 TRAINEE-TRAINING PROGRAM GRADUATE HOUR 500 500*

*©0042 \*Specialty Items*

FILE NAME =	USER NAME = pr2009-0110	DESIGNED -	REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MANHATTAN-MONEE ROAD (SCHOOLHOUSE RD. TO CENTER RD.) SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C:\pr_2009\pr2009-0110\02000001034111.sht	PLANT	DRAWN -	REVISIONS -			531	40X-RS-9	WILL	18	3
PLANT SCALE = 100,000' / 1"	CHECKED -	REVISIONS -	REVISIONS -			CONTRACT NO. 60N71				
PLANT DATE = 11/14/2013	DATE -	REVISIONS -	REVISIONS -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				