



PLAN VIEW

NOTES:

- EXPANSION JOINTS SHALL BE CONSTRUCTED AS SHOWN ON THE DETAILS FOR P.C.C. SIDEWALK.
- THE CURB BETWEEN ADJACENT DRIVEWAYS SHALL BE FULL HEIGHT FOR A DISTANCE OF AT LEAST FOUR 4 FEET (1.2 METERS)
- P.C. CONCRETE DRIVEWAYS SHALL BE CONSTRUCTED AT LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
- 4. ¾4" (20) PREFORMED EXPANSION JOINTS WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO P.C.C. DRIVEWAY PAVEMENT 8" (200).
- 5. COMBINATION CONC. CURB AND GUTTER SHALL BE MEASURED STRAIGHT ACROSS THE DRIVEWAY. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR THE TRANSITION CURB AND GUTTER.





P.C.C. DRIVEWAY PAVEMENT DETAIL

ADJACENT BUILDING, RETAINING WALL OR OTHER STRUCTURE SIDEWALK -R.O.W. (20) └KEYSTONE-DRIVEWAY . - SOD --SIDEWALK APRON RAMP SIDEWALK TO MEET CURB CURB AND GUTTER -DEPRESSED CURB FIRE HYDRANT PLATFORM TRAFFIC SIGNAL, TROLLEY POWER THE PROPOSED CARRIAGE WALK SHALL DEPRESSED CURB POLE, LIGHT STANDARD OR COLUMN FOR OVERHEAD STRUCTURE. TO BE 3'-0" (0.9 m) SQUARE OR AS DIRECTED BY THE ENGINEER. BE CONSTRUCTED THE SAME WIDTH AND LENGTH AS THE EXISTING CARRIAGE WALK AND PAID FOR AS PORTLAND CEMENT CONCRETE SIDEWALK, 5-INCHES (125). — PAVEMENT 🦯 PAVEMENT -


SLOPE FOR SIDEWALK 1" (25) IN 3'-0" (0.9 m) IN CHICAGO


NOTES:

- ONE-HALF INCH THICK EXPANSION JOINTS SHALL BE PLACED BETWEEN THE SIDEWALK AND ALL STRUCTURES SUCH AS LIGHT STANDARDS, TRAFFIC LIGHT STANDARDS, MANHOLES, WHICH EXTEND THROUGH THE SIDEWALK.
- 2. ¾4" (20) THICK EXPANSION JOINTS SHALL BE PLACED AT INTERVALS OF NOT MORE THAN 100 FEET (30 METERS) IN THE SIDEWALK. WHERE THE SIDEWALK IS CONSTRUCTED ADJACENT-TO PAYEMENT OR CURB HAVING EXPANSION JOINTS, THE EXPANSION JOINTS IN THE SIDEWALK SHALL BE PLACED OPPOSITE THE EXISTING EXPANSION JOINTS AS NEARLY AS PRACTICABLE. EXPANSION JOINTS SHALL ALSO BE PLACED WHERE THE SIDEWALK ABUTS EXISTING SIDEWALKS, BETWEEN DRIVEWAY PAYEMENT AND SIDEWALK, AND BETWEEN SIDEWALK AND CURBS WHERE THE-SIDEWALK ABUTS A CURB.

PORTLAND CEMENT CONCRETE SIDEWALK DETAILS

NOTES: NO EXTRA COMPENSATION SHALL BE ALLOWED FOR THE GUTTER FLARE





ALLEY RETURN DETAIL

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN

FILE NAME =	USER NAME = patelp2	DESIGNED -	M. DE YONG	REVISED -			CITY OF CHICAGO			F.A.I. S	ECTION	COUNTY	TOTAL SHEET
pw:\\388039-pwintl.aecomonline.local:PWAE	OM00\Documents\01 Americas\Transportation\6	Ø D€9AWN Circle∖Ph	ase_II\000_CAD\006_Road		11 Detail-04.dgn STATE OF ILLINOIS	DETAILS :				• 20	13-007R	соок	317 236
	PLOT SCALE = 49.9999 '/ in.	CHECKED -		REVISED -	DEPARTMENT OF TRANSPORTATION	DETAILS FOR P.C. CONCRETE DRIVEWAY, ALLEY RETURN AND SIDEWALK SCALE: NONE SHEET NO. 4 OF 31 SHEETS STA. TO STA.			VALK	BD400-03	(BD-17)		T NO. 60W25
	PLOT DATE = 5/15/2013	DATE -	06-13-90	REVISED -						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID			
										• 90/94/290			