ROUTE	US 30 (IL 47 to DeKalb C	County Line)		(Continued)			
CROSS	CROSS STREET		LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD
		EB		3	200	600	67
		EB		12	60	720	80
		EB		6	50	300	33
		EB		12	6	72	8
		EB		6	25	150	17
		EB		12	6	72	8
		EB		12	6	72	8
	Big Rock Creek	EB		3	30	90	10
Big Rock Creek		EB		3	100	300	33
		EB		3	50	150	17
		EB		12	6	72	8
		EB		12	30	360	40
		EB		12	6	72	8
		EB		12	30	360	40
		EB		12	6	72	8
		EB		12	8	96	11
		EB		3	150	450	50
	Davis Rd	EB		12	6	72	8
Dauberman Rd		EB		3	10	30	3
Baaboilliailita		EB		3	40	120	13
		EB		3	30	90	10
		EB		12	100	1200	133
		EB		3	150	450	50
		EB		6	30	180	20
		EB		12	8	96	11
		EB		3	20	60	7
		EB		12	10	120	13
		EB		3	40	120	13
		EB		3	150	450	50
		EB		3	150	450	50
		EB		3	30	90	10
		EB		3	100	300	33
		EB		3	200	600	67
	Dugan Rd	EB		3	200	600	67
Dugan Dd	Dugan Ku	EB		3	250	750	83
Dugan Rd		EB		3	100	300	33
		EB		3	20	60	7
		EB		3	300	900	100
		EB		3	100	300	33
		EB		3	50	150	17
		EB		3	50	150	17
		EB		3	125	375	42
		EB		3	200	600	67
				3			
		EB			200	600	67
	M. mi - in - I D.:	EB		3	30	90	10
M L.D.	Municipal Dr	EB	_	3	30	90	10
Municipal Dr		EB	2	3	100	300	33
	<u> </u>	EB	2	12	6	72	8
	IL 47	EB	2	3	125	375	42
					10.55-		
		TOTALS:			13605		5424
					FT		SY

CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAI
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YE
IL-47		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB EB	1	12 12	4	48 48	5 5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB EB	2	12 12	4	48 48	5 5
	Galena Blvd	EB	2	12	4	48	5
Galena Blvd	Galeria bivu	EB	1	6	10	60	7
Galelia Divu		EB	1	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	8	6	48	5
		EB	2	12	4	48	5
	Hankes Rd	EB	2	12	4	48	5
Hankes Rd		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
	I-88	EB	2	12	4	48	5
I-88		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	2	12	4	48	5
		WB	2	12	4	48	5
		WB WB	2 2	12 12	4	48 48	5 5
		WB	2	12	4	48	5
		WB	2	12	4	48	5
		WB	2	12	4	48	5
		WB	2	12	4	48	5
		WB	2	12	4	48	5
		WB	2	12	4	48	5
		WB	2	12	4	48	5
		WB	2	12	4	48	5
	IL-47	WB	2	12	4	48	5
		TOTALS:			228		295

FILE NAME =	USER NAME = PencePL	DESIGNED -	REVISED -
c:\pw_work\pwidot\pencepl\d0335178\HMA-I	(ANE-Design.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -
	PLOT DATE = 5/22/2013	DATE -	REVISED -

SCALE:

INTERMITTENT RESURFACING SCHEDULE				F.A RTE.	SECTION COUNTY				
US 30 & IL 56					VAR.	2013-029 RS	KANE		
03 30 & 1L 30						CONTRACT	N		
	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			