GENERAL NOTES

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

AT&T (309/757-4707) MidAmerican Energy Co. – Elec. (309/793-3833) MidAmerican Energy Co. – Gas (309/793-3707)

IDOT is not a member of JULIE. If you are near any overhead lighting, intersection lighting or traffic signals, contact the IDOT Traffic Office at 815/284-5469 at least 48 hours prior to work.

The applicable portions of Article 105.07 of the Standard Specification shall apply except for the following: The Contractor shall be responsible to locate the vertical depths of the underground utilities which may interfere with construction operations. This work will not be measured or paid for separately, but shall be considered as included in the unit bid price for the item of construction involved.

Per SB 699 (90 day utility relocation law), once right-of-way is clear to award the project, a notice will be sent to the utility companies instructing them to have their facilities relocated within 90 days. Estimated date relocation complete = Award Date + 100 days.

Tie bars shall be installed to tie PCC appurtenance to adjacent existing concrete pavement.

Tie the following

to the existing concrete pavement

Length, size, and spacing of Tie Bars

Gutter or Curb & Gutter

Std. 606001

24" long No. 6 @ 24" centers

PCC Base Course

Std. 353001

24" long No. 6 @ 30" centers

Tie bars to be installed in accordance with the applicable portions of Article 420.05(b) of the Standard Specifications. See Highway Standard 420001 for detail on longitudinal construction joint grouted-in-place tie bar. The cost of the tie bars to be included in the cost of the PCC appurtenance adjacent to the existing pavement.

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

It shall be the Contractor's responsibility to contact the municipality to determine approved methods of utility structure adjustment. Utility structures may include, but are not limited to, manholes, water valves, handholes, etc. All materials and work necessary to complete adjustments per municipality requirements shall be considered included in the cost of the associated adjustment pay item.

COMMITMENTS

- We extended the driveway at RT Sta. 1012+72 to accommodate partial aggregate FE so property owner can get into his field.
- Save the 3 big trees within the ROW at RT Sta. 975+40 to RT Sta. 975+90 (outside construction limits).
- Replace some of trees in front of property from RT Sta. 976+07 to RT Sta. 976+67. RE shall contact property owner George Stevens at (815) 766-7743 prior to installation of trees.
- 4. No heavy equipment shall be placed within the easements between RT Sta. 976+67 to RT Sta. 980+68 due to the septic systems installed close to existing ROW. All earthwork within these areas shall be fill only. Lawns shall be returned to mowable condition when all work on the properties is completed.
- The Contractor shall place temporary fence 5' south of the existing ROW line (within the temporary easement) at George Stevens' property from RT Sta. 978+68 to RT Sta. 979+68. The Contractor shall not be allowed upon Mr. Stevens' property, including any area of temporary easement, beyond the south side of the temporary fence. The Contractor shall assume liability for any damages south of the temporary fencing due to contractor negligence.
- Remove all trees within the driveway limits up to the existing ROW at RT Sta. 847+69, RT Sta. 851+68, RT Sta. 860+86, RT Sta. 864+37 & RT Sta. 867+57.
- 7. The contractor shall not touch the fence and gate from RT Sta. 976+67 to RT Sta. 977+70. Landscape rocks around the property owner's driveway culvert (if they are still there during construction), shall be returned to the property owner. Contact property owner Susan Meredith at (309) 738-5523. Lawn shall be returned to mowable condition when work on the property is completed.
- Lawn at LT Sta. 975+10 to LT Sta. 976+75 shall be returned to mowable condition when work on the property is completed. Property owner would like us to try to save the 55" diameter tree near the culvert, but they understand if we cannot.
- The property owner at LT Sta. 960+23 to LT Sta. 962+23 (David Lund) has signed a Temporary Use Permit if it is needed in the construction process.
- 10. The boat ramp at LT Sta. 823+92 shall be closed. Aggregate in the boat ramp area shall be removed up to the existing ROW, filled in with earth excavation from the project and seeded. This work shall be included in the cost per cubic yard for Earth Excavation and included in the cost per acre for Seeding of the type specified in the plans.
- 11. The large rock at approximate Station 960+73 RT (approximate 55' offset) shall be moved and returned to the property owner. Care shall be taken to not cause any major damage the rock. The Contractor shall contact Monte Hines at (309) 314-7726 to determine the final destination of the rock. The cost of moving the rock shall be included in the cost of Earth Excavation.

BIOLOGICAL COMMITMENTS

- This project will impact a total of 0.165 acre of regulatory wetlands. These impacts will be mitigated by purchasing 0.403 acre of wetland bank credits from the Andalusia Slough Wetland Bank.
- All wetland boundaries in the project limits shall be shown on the contract plans.
- The construction limits in front of the wetland sites shall be marked in the field with snow fence.
- 4. No construction activities shall take place beyond the construction limits in the wetland sites. This includes driving and parking vehicles and stock piling materials.
- No construction activity shall occur in Loud Thunder Forest Preserve.

USER NAME * DESIGNED - Engineering Systems REVISED -	<u> </u>	ROUTE SECTION	COUNTY MOTE NO
FILE NAME + 64H11, GN, DOCX REMSED - STATE OF ILLINOIS	GENERAL NOTES	FAP 599 (83MFT & 103MFT)N	Rock island 340 12
PLOT SCALE - CHECKED - REMSED - DEPARTMENT OF TRANSPORTATION		(ii. 92)	CONTRACT NO. 64H11
PLOT DATE * 5142013 7:54 AM DATE - 2/28/2013 3:43 FM REVISED -	SCALE: SHEET NO, OF SHEETS STA TO STA	ILLINO	IS FED, AID PROJECT