

# HOT-MIX ASPHALT SCHEDULE

STATIONING		REMARKS	H.M.A.		H.M.A. AREA SO. YD.	* BIT PRIME (2 COATS) POUND	* H.M.A. SURF REM BUTT JOINT SQ. YD.	* P.C.C. SURF REM BUTT JOINT SQ. YD.	* TEMP. RAMP SO. YD.	LEVEL BINDER (MM) IL 9.5FG, N50 TON	H.M.A. SURF. CSE. MIX "C", N50 TON
			LENGTH FEET	WIDTH FEET							
IL 92 - MAINLINE (Including 3' Widening on Each Side)											
802+15.0	- 802+90.0	Butt Joint - No Widening	75	20	167	190.67	100.0		11.1	2.5	13.4
802+90.0	- 950+70.0		14780	26	42698	48846.26				2988.8	3586.6
950+70.0	- 951+45.0	Butt Joint - Cool Creek	75	26	217	247.87	130.0		14.4	3.2	17.4
951+45.0	- 952+43.0	Omission - Bridge	98	26		0.00					
952+43.0	- 953+18.0	Butt Joint - Cool Creek	75	26	217	247.87	130.0		14.4	3.2	17.4
953+18.0	- 994+89.0		4171	26	12050	13784.69				843.5	1012.2
994+89.0	- 995+64.0	Butt Joint - New Concrete	75	26	217	247.87		130.0	14.4	2.4	18.2
995+64.0	- 997+03.0	Omission - New Concrete	139	26		0.00					
997+03.0	- 997+78.0	Butt Joint - New Concrete	75	26	217	247.87		130.0	14.4	3.2	17.4
997+78.0	- 1017+84.0		2006	26	5795	6629.61				405.7	486.8
1017+84.0	- 1018+59.0	Butt Joint - No Widening	75	20	167	190.67	100.0		11.1	2.5	13.4

\* ADDITIONAL QUANTITIES ON ENTRANCE SCHEDULE

FILE NAME *	USER NAME : granton	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>HOT-MIX ASPHALT SCHEDULE</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
c:\pwwork\pwwork\granton\08261271\0287						DRAWN -	REVISED -	599	(83MFT & 103MFT)W	ROCK ISLAND	340	36
Default						CHECKED -	REVISED -	CONTRACT NO. 64H11				
PLOT SCALE : 50.0000 "/ in.						DATE -	REVISED -	ILLINOIS FED. AID PROJECT				