

ENTRANCE SCHEDULE

LOCATION	NEW ENT. TYPE	NOTE	** TOTAL	** TOTAL	TOTAL	TOTAL	TOTAL	TOTAL	TOTAL	X4060110	35101400	42300300	40800050	40600985	44000200	
			AGG	HMA	NEW CONC	OLD CONC	AGG	HMA	NEW CONC	AGG	PRIME	AGG	PCC DRWV	INC	*PCC SURF	DRIVEWAY
			AREA	AREA	AREA	AREA	AREA	AREA	AREA	COAT	BASE CSE	7"	HMA	REM-BUTT	PVMT	
SO FT	SO FT	SO FT	SO FT	SO YD	SO YD	SO YD	SO YD	POUND	TON	SY	TON	SO YD	SO YD			
945+58	PE/MB	LT	HMA		1090.0	961.0			121.1	106.8						
947+68	PE	LT	HMA		1234.0	1132.0			137.1	125.8						
947+90	140th St W	RT	HMA	3" Inc HMA	3485.0	3311.0			387.2	367.9						
948+60	2 PE's/MB	LT	HMA		798.0	733.0			88.7	81.4						
955+08	CE	LT	HMA		899.0	862.0			99.9	95.8						
955+11	CE/MB	RT	HMA		823.0	672.0			91.4	74.7						
955+56	MB between driveways	LT	HMA		152.0	114.0			16.9	12.7						
956+07	CE/MB	LT	HMA		1252.0	1112.0			139.1	123.6						
959+66	CE/MB	RT	HMA		2272.0	2131.0			252.4	236.8						
961+07	PE	LT	HMA		629.0	569.0			69.9	63.2						
961+40	MB between driveways	LT	HMA		106.0	79.0			11.8	8.8						
961+53	PE/MB	RT	HMA		1076.0	939.0			119.6	104.3						
961+73	PE/MB	LT	HMA		830.0	693.0			92.2	77.0						
961+89	PE	RT	HMA		898.0	798.0			99.8	88.7						
963+35	PE	LT	HMA		695.0	626.0			77.2	69.6						
963+99	PE/MB	RT	HMA		1224.0	706.0			136.0	78.4						
964+08	MB between driveways	LT	HMA		432.0	325.0			48.0	36.1						
964+83	PE/MB	LT	HMA		1049.0	919.0			116.6	102.1						
965+76	PE/MB	RT	HMA		909.0	782.0			101.0	86.9						
966+33	PE	RT	HMA		823.0	729.0			91.4	81.0						
966+95	PE/MB	LT	HMA		957.0	830.0			106.3	92.2						
967+34	PE/MB	RT	HMA		910.0	726.0			101.1	80.7						
968+18	FE	RT	AGG		1086.0				120.7							
969+34	PE	LT	CONCRETE	Concrete	807.0		721.0	383.0	89.7		80.1				42.56	
970+20	MB between driveways	LT	HMA		531.0	399.0			59.0	44.3						
970+21	PE/MB	RT	HMA		1305.0	1181.0			145.0	131.2						
971+05	PE/MB	LT	CONCRETE	Concrete	867.0		756.0	81.0	96.3		84.0				9.00	
973+46	126th St W	RT	HMA	12" agg, 3" Inc HMA	2083.0	1963.0			231.4	218.1						
973+56	PE/MB	LT	HMA		868.0	751.0			96.4	83.4						
975+28	PE/MB	RT	HMA		988.0	849.0			109.8	94.3						
976+56	FE	RT	AGG		815.0				90.6							
976+75	2 joined PE's/MB	LT	HMA		1908.0	1731.0			212.0	192.3						
976+90	PE	RT	HMA		665.0	614.0			73.9	68.2						
977+65	MB between driveways	RT	HMA		411.0	308.0			45.7	34.2						
978+34	PE	RT	HMA		622.0	566.0			69.1	62.9						
978+90	MB between driveways	RT	HMA		276.0	207.0			30.7	23.0						
979+43	PE	RT	HMA		618.0	562.0			68.7	62.4						
979+76	MB between driveways	RT	HMA		104.0	78.0			11.6	8.7						
980+09	PE	RT	HMA		633.0	573.0			70.3	63.7						
981+69	PE/MB	RT	HMA		804.0	707.0			89.3	78.6						
983+45	FE	RT	AGG		1088.0				120.9							
983+72	PE	LT	HMA		992.0	883.0			110.2	98.1						
984+91	PE/MB	LT	HMA		1465.0	1324.0			162.8	147.1						
985+40	FE	RT	AGG		1358.0				150.9							
987+37	PE/MB	RT	HMA		871.0	754.0			96.8	83.8						
989+86	PE/MB	RT	HMA		869.0	752.0			96.6	83.6						
991+84	PE/MB	RT	HMA		886.0	769.0			98.4	85.4						
992+43	121st St W	LT	HMA	12" agg, 3" Inc HMA	1884.0	1766.0			209.3	196.2						
993+35	Bomb CT	RT	HMA		974.0	858.0			108.2	95.3						
994+31	PE/MB	LT	HMA		667.0		604.0	333.0	74.1		67.1				37.00	