

# PAVEMENT PATCHING SCHEDULE

BEGIN STATION	REMARKS	44200120		44200124		44200126		44200156		44200160		44200162		30300001		Z0028415			
		LENGTH OF		AREA OF		PAVEMENT		PAVEMENT		PAVEMENT		PAVEMENT		PAVEMENT		AGG			
		PATCH (FEET)		PATCH (SQ YD)		PATCHING		PATCHING		PATCHING		PATCHING		PATCHING		SUBGRADE IMPROV.		GEOTECH. REINF.	
		LT LANE	RT LANE	LT LANE	RT LANE	TYPE 2, 10" (SQ YD)		TYPE 3, 10" (SQ YD)		TYPE 4, 10" (SQ YD)		TYPE 2, 13" (SQ YD)		TYPE 3, 13" (SQ YD)		TYPE 4, 13" (SQ YD)		CU. YD.	SQ. YD.
WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB				
802+28	Overlaid Concrete		8	0.00	8.89						8.89					1.48	8.89		
804+50	Overlaid Concrete		160	0.00	177.78								177.78			29.63	177.78		
805+00	Overlaid Concrete	6	6	6.67	6.67					6.67	6.67					2.22	13.33		
806+45	Overlaid Concrete		6	0.00	6.67						6.67					1.11	6.67		
807+64	Overlaid Concrete	6	6	6.67	6.67					6.67	6.67					2.22	13.33		
807+89	Overlaid Concrete		6	0.00	6.67						6.67					1.11	6.67		
808+90	Overlaid Concrete		8	0.00	8.89						8.89					1.48	8.89		
809+89	Overlaid Concrete	6	6	6.67	6.67					6.67	6.67					2.22	13.33		
810+92	Overlaid Concrete	6	8	6.67	8.89					6.67	8.89					2.59	15.56		
811+73	Overlaid Concrete	6		6.67	0.00					6.67						1.11	6.67		
813+01	Overlaid Concrete	25	128	27.78	142.22								27.78	142.22		28.33	170.00		
813+39	Overlaid Concrete	6	6	6.67	6.67					6.67	6.67					2.22	13.33		
813+92	Overlaid Concrete	6	6	6.67	6.67					6.67	6.67					2.22	13.33		
814+39	Overlaid Concrete	6	6	6.67	6.67					6.67	6.67					2.22	13.33		
814+91	Overlaid Concrete	6	6	6.67	6.67					6.67	6.67					2.22	13.33		
815+61	Overlaid Concrete		6	0.00	6.67						6.67					1.11	6.67		
816+32	Overlaid Concrete	6		6.67	0.00					6.67						1.11	6.67		
818+94	Overlaid Concrete		10	0.00	11.11						11.11					1.85	11.11		
824+03	Concrete	6	6	6.67	6.67	6.67	6.67									2.22	13.33		
824+27	Concrete	6	6	6.67	6.67	6.67	6.67									2.22	13.33		
828+27	Concrete	6		6.67	0.00	6.67										1.11	6.67		
830+09	Concrete		6	0.00	6.67		6.67									1.11	6.67		
832+74	Concrete		6	0.00	6.67		6.67									1.11	6.67		
834+13	Concrete		6	0.00	6.67		6.67									1.11	6.67		
835+14	Concrete		10	0.00	11.11		11.11									1.85	11.11		
837+97	Concrete		6	0.00	6.67		6.67									1.11	6.67		
842+22	Concrete	6	6	6.67	6.67	6.67	6.67									2.22	13.33		
843+44	Start of Overlay	6	6	6.67	6.67					6.67	6.67					2.22	13.33		
846+05	Overlaid Concrete	22		24.44	0.00							24.44				4.07	24.44		
846+13	End of Overlay at		14	0.00	15.56							15.56				2.59	15.56		
847+27	Concrete		8	0.00	8.89		8.89									1.48	8.89		
850+31	Concrete	6		6.67	0.00	6.67										1.11	6.67		
851+78	Concrete		6	0.00	6.67		6.67									1.11	6.67		
857+42	Concrete	10		11.11	0.00	11.11										1.85	11.11		
858+42	HMA Patch in Concrete Section		8	0.00	8.89		8.89									1.48	8.89		
859+48	Concrete		12	0.00	13.33		13.33									2.22	13.33		
866+52	Concrete	6		6.67	0.00	6.67										1.11	6.67		
871+19	Concrete	6		6.67	0.00	6.67										1.11	6.67		
877+77	Concrete	6	6	6.67	6.67	6.67	6.67									2.22	13.33		
878+53	Concrete	12		13.33	0.00	13.33										2.22	13.33		
879+85	Concrete	12	12	13.33	13.33	13.33	13.33									4.44	26.67		

\* AT ENGINEERS DISCRETION

\*\* ADDITIONAL QUANTITY ON SCHEDULE OF QUANTITIES

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PAVEMENT PATCHING SCHEDULE</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
Default	es:\pw_work\pwork\grantpm\d0261271\020711-sh-t-schedule.dgn	DRAWN -	REVISED -			599	(83MFT & 103MFT)W	ROCK ISLAND	340	42	
	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -			CONTRACT NO. 64H11					
	PLOT DATE = Wed Mar 20 11:04:57 2013	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					