

# PAVEMENT PATCHING SCHEDULE

BEGIN STATION	REMARKS	LENGTH OF		AREA OF		44200120 PAVEMENT		44200124 PAVEMENT		44200126 PAVEMENT		44200156 PAVEMENT		44200160 PAVEMENT		44200162 PAVEMENT		30300001 AGG	Z0028415 **
		PATCH (FEET)		PATCH (SQ YD)		PATCHING		PATCHING		PATCHING		PATCHING		PATCHING		PATCHING		SUBGRADE IMPROV.	GEOTECH. REINF.
		LT LANE	RT LANE	LT LANE	RT LANE	TYPE 2, 10" (SQ YD)		TYPE 3, 10" (SQ YD)		TYPE 4, 10" (SQ YD)		TYPE 2, 13" (SQ YD)		TYPE 3, 13" (SQ YD)		TYPE 4, 13" (SQ YD)		CU. YD.	SQ. YD.
		WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB		
935+24	Overlaid Concrete	6	6	6.67	6.67							6.67	6.67					2.22	13.33
938+32	Overlaid Concrete	6		6.67	0.00							6.67						1.11	6.67
939+50	Overlaid Concrete	6		6.67	0.00							6.67						1.11	6.67
940+42	Overlaid Concrete	16	16	17.78	17.78									17.78	17.78			5.93	35.56
941+48	Overlaid Concrete	12		13.33	0.00							13.33						2.22	13.33
942+54	Overlaid Concrete	6		6.67	0.00							6.67						1.11	6.67
942+74	Overlaid Concrete		8	0.00	8.89								8.89					1.48	8.89
943+53	Overlaid Concrete	6		6.67	0.00							6.67						1.11	6.67
945+57	Overlaid Concrete	6		6.67	0.00							6.67						1.11	6.67
949+62	Overlaid Concrete	8	8	8.89	8.89							8.89	8.89					2.96	17.78
958+34	End of Overlay (old patch is HMA and Concrete)	15	15	16.67	16.67									16.67	16.67			5.56	33.33
959+86	Concrete	10		11.11	0.00	11.11												1.85	11.11
967+98	Concrete	10		11.11	0.00	11.11												1.85	11.11
984+21	Concrete	12		13.33	0.00	13.33												2.22	13.33
984+99	Concrete		25	0.00	27.78					27.78								4.63	27.78
1003+88	Concrete (old patch has HMA overlay)		9	0.00	10.00		10.00											1.67	10.00
1005+18	Concrete	17		18.89	0.00		18.89											3.15	18.89
1017+90	Concrete	6	6	6.67	6.67	6.67	6.67											2.22	13.33
	* Contingency Quantity					18.00	18.00	13.00	13.00	15.00	15.00	18.00	18.00	13.00	13.00	15.00	15.00	30.67	184.00
<b>SUBTOTAL</b>						186.89	179.11	31.89	13.00	15.00	42.78	406.89	290.22	111.89	123.00	118.33	462.78	330.30	1981.78
<b>GRAND TOTAL</b>						366.00		44.89		57.78		697.11		234.89		581.11			
<b>10% OF GRAND TOTAL</b>																		33.03	198.18

\* AT ENGINEERS DISCRETION

\*\* ADDITIONAL QUANTITY ON SCHEDULE OF QUANTITIES