

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		MADISON 80% FED 20% STATE 0005	ST. CLAIR 80% FED 20% STATE 0005
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	508	508	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	45954	6499	39455
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	662	662	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	864	66	798
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	105	33	72
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	972	722	250
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	249	51	198
78300100	PAVEMENT MARKING REMOVAL	SQ FT	72		72
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	249	51	198
X0326898	CENTER LINE - RUMBLE STRIP - 16"	FOOT	1361	361	1000
X2020700	SHOULDER SHAPING, SPECIAL	UNIT	199	75.9	123.1

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		MADISON 80% FED 20% STATE 0005	ST. CLAIR 80% FED 20% STATE 0005
* Z0036200	PAINT CURB	FOOT	372	372	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HOOR</del>			
<del>Z0076604</del>	<del>TRAINEES TRAINING PROGRAM GRADUATE</del>	<del>HOOR</del>			
4420110	CLASS B PATCHES, TYPE II, 24 INCH	SQ YD	54	16	38
4420130	CLASS B PATCHES, TYPE IV, 24 INCH	SQ YD	119	67	52

\*SPECIALTY ITEM

FILE NAME =	USER NAME = millerj	DESIGNED -	REVISED -
c:\pwork\p\dot\millerj\d8338686\d8338686-ehs-plot.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / 1"		CHECKED -	REVISED -
PLOT DATE = 5/10/2013		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE. 9166	SECTION 510RS-3, 90RS-1	COUNTY *	TOTAL SHEETS 34	SHEET NO. 4
CONTRACT NO. 76G36				*ST. CLAIR AND MADISON
ILLINOIS FED. AID PROJECT				