

MODEL Default
FILE Name: P:\Galesburg\21\res123081.IDOT - DIST 4 - PTB 2014\0323\Work Order 08 - FY 2023 Slope Repair\18_TrafficSummary.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				FULTON COUNTY					
				100% STATE					
				0005					
				RURAL					
20100500	TREE REMOVAL, ACRES	ACRE	0.5	0.5					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	895	895					
20400800	FURNISHED EXCAVATION	CU YD	250	250					
20700110	POROUS GRANULAR EMBANKMENT	TON	4	4					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	10	10					
28000400	PERIMETER EROSION BARRIER	FOOT	550	550					
28100207									
28100107	STONE RIPRAP, CLASS A4	TON	1433	1433					
28100209									
28100109	STONE RIPRAP, CLASS A5	TON	774	774					
28200200	FILTER FABRIC	SQ YD	1632	1632					
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	75	75					
44004250	PAVED SHOULDER REMOVAL	SQ YD	353	353					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	353	353					
50800105	REINFORCEMENT BARS	POUND	17	17					
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	1	1					

1

KLINGNER
& ASSOCIATES, P.C.

Engineers • Architects • Surveyors
www.klinger.com
Galesburg, Illinois
40 North Prairie Street
3010-3010-0000

Quincy, IL, Hannibal, MO
Burlington, IA, Pella, IA, Columbia, MO
Davenport, IA, Cantonville, IL

USER NAME = aschafer	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 40,0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 5/6/2024	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAP 317 (US 24)
SUMMARY OF QUANTITIES

SCALE: NONE SHEET 1 OF 3 SHEETS STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(137,102)SLP,PP	FULTON	22	3
CONTRACT NO. 68H92				
ILLINOIS FED. AID PROJECT				