


SINKHOLE	FILLING QUAN	NTITIES			
SINKHOLE #	EARTH EXC.	FURNISHED EXC.	RR FILL	CONC .FILL	SPEC. EXC.
1		1564 C.Y.	25 TON	20 C.Y.	872 C.Y.
2		90 C.Y.			
3		474 C.Y.	25 TON	20 C.Y.	522 C.Y.
4		262 C.Y.	25 TON	20 C.Y.	738 C.Y.
5	117 C.Y.	329 C.Y.	25 TON	20 C.Y.	315 C.Y.
TOTAL	117 C.Y.	2719 C.Y.	100 TON	80 C.Y.	2447 C.Y.





NOTE:
THE CONTRACTOR SHALL USE EXTREME CAUTION WHEN WORKING IN THE AREA OF THE SHAFTS DUE TO THE UNKNOWN CONDITION OF THE SHAFTS AND THE UNKNOWN STABILITY OF THE AREA AROUND THE SHAFTS. THE ENGINEER RESERVES THE RIGHT TO INCREASE OR DECREASE THE VOLUME OF SPECIAL EXCAVATION AND BACKFILLING MATERIALS REQUIRED. THE ENGINEER WILL MAKE THE DETERMINATION DURING CONSTRUCTION BASED ON THE EXACT CONDITIONS ENCOUNTERED DURING THE SPECIAL EXCAVATION PROCESS. AFTER INSTALLATION OF THE RIPRAP, THE CONTRACTOR SHALL TEMPORARILY FENCE THE EXCAVATION AND WAIT FOR 7 DAYS, PRIOR TO COMPLETION OF THE REMAINING FILL.



State of Illinois Department of Natural Resources

No. 6 Mine Group Reclamation Project AML-GWmE-0510 Williamson County

Date: May 2007			
3y: M.T.	d By:		
Drawn By	Checked By:		

Detail Sheet Sheet

ō

<u>8</u>