F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99-1 AC-RS-3	WILL	14	2
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO.: 60C58

INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES
3	SUMMARY OF QUANTITES
4	EXISTING & PROPOSED TYPICAL SECTIONS
5-6	EXISTING AND PROPOSED ROADWAY PLANS
7-8	EXISTING AND PROPOSED PAVEMENT MARKING PLANS
9	BUTT-JOINT AND HMA TAPER DETAILS
10	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT
11	TRAFFIC CONTROL & PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
12	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
13	TRAFFIC CONTROL AND PROTECTION AND TURN BAYS (TO REMAIN OPEN TO TRAFFIC)
14	ARTERIAL ROAD INFORMATION SIGN

STATE STANDARDS

000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
701006-02	OFF-ROAD OPERATIONS 2L, 2W, 4.5M (15') TO PAVEMENT EDGE FOR SPEEDS 45 MPH
701011-01	OFF-ROAD OPERATIONS 2L, 2W DAY ONLY FOR SPEEDS ≥ 45 MPH
701201-02	LANE CLOSURE 2L, 2W DAY ONLY ON-ROAD TO 600 MM (24") OFF-ROAD FOR SPEEDS ≥ 45 MPH
701301-02	LANE CLOSURE 2L, 2W SHORT TIME OPERATIONS
701306-01	LANE CLOSURE 2L, 2W SLOW MOVING OPERATIONS-DAY ONLY FOR SPEEDS ≥ 45 MPH
701311-02	LANE CLOSURE 2L, 2W MOVING OPERATIONS-DAY ONLY
701501-03	URBAN LANE CLOSURE 2L, 2W UNDIVIDED
702001-06	TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED).

THE MAXIMUM GRADE DIFFERENTIAL BETWEEN LANES SHALL NOT EXCEED 40MM (1-1/2 INCHES) WHERE THE SPEED LIMIT IS 80 KM/H (45 MPH) OR LESS AND 25MM (1 INCH) WHERE THE SPEED LIMIT IS GREATER THAN 80 KM/H (45 MPH).

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.

CONTRACTOR WILL NOT BE ABLE TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE RESIDENT ENGINEER SHALL VERIFY THE LOCATIONS OF ALL EXISTING PAVEMENT MARKINGS PRIOR TO PULVERIZATION OR RESURFACING

THE RESIDENT ENGINEER SHALL CONTACT Ms. CORA MATHIS, AREA TRAFFIC FIELD ENGINEER AT (815) 485-6475, A MINIMUM OF TWO WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

THE CONTRACTOR SHALL CONTACT THE ARTERIAL TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAI 55: I-55 EAST FRONTAGE ROAD

INDEX OF SHEETS, GENERAL NOTES AND STATE STANDARDS

SCALE: VERT. HORIZ. DRAWN BY

DATE 6/21/2007 CHECKED BY