

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES)
UNLESS OTHERWISE SHOWN.

REVISIONS
NAME
DATE
R. MIRS
9-15-97
T. RAMMACHER
2-2-99
T. RAMMACHER
2-2-99
T. RAMMACHER
SCALE:
DRAWN BY DESIGN
DATE: 1/3/2007
CHECKED BY

PLOT DATE = 1/3/2007 LIE NAME = a.hpro.jano.yal00403\ah..rdwy.dgn PLOT SCALE = 50.2000 v/ IN. USER NAME = drivakosgn

REVISION DATE: 02/02/99