

MOUTE NO.	SECT ION	COUNTY		TOTAL SHEETS	SHEET NO.
F.A.I. 94	2006-043 RS	соок		135	118
FED. ROAD 0157. NO. 7		ILL INDIS	FED AID PROJECT-		

Contract # 62747



DESIGN STRESSES

 $f_y = 60,000 \text{ psi} (reinforcement)$

–∉ Brg. S. Abut.

-∉ Edens

Expressway

SCOPE OF WORK

f'c = 3,500 psi

- 1. Provide Protective Shield with limits as indicated,
- 2. Perform substructure repairs (structural repair of
- concrete and epoxy crack injection). <u>Stage II:</u> 3. Close Stage II construction areas to traffic.
- 4. Hydro-Scarify the deck slab.
- 5. Remove and replace expansion joints and surrounding concrete (including parapets).
- 6. Perform deck slab repair.
- 7. Adjust existing scuppers and install new arate.
- 8. Place Overlay.
- 9. Place temporary roadway transitions.
- 10. Open Stage II Removal area to staged traffic. Stage III:
- 11. Close Stage III Removal areas to traffic.
- 12. Repeat steps 4-9 but for Stage III construction.
- 13. Open bridge to traffic.

NOTES

- 1. For joint removal and replacement plans and details, see Sheet No. 121 thru 122b
- 2. See Structural Notes on Sheet No. 118a

<u>LEGEND</u>



Concrete Removal / Joint Reconstruction



<u>GENERAL PLAN & ELEVATION</u> <u>F.A.I. 94/ (EDENS EXPRESSWAY)</u> <u>OVER NORTH BRANCH</u> <u>COOK COUNTY</u> <u>STATION 23+63.00</u> <u>STRUCTURE NO. 016-0107</u>